

Indian Statistical Institute
Delhi Centre
Notice Inviting Tender

NIT No- D / ISI /Civil Work /2018-19 / 355

Dated 28/05/2018

Name of work : Providing and Fixing of Existing Window AC with Renewal wooden frame in Faculty Building/GH/Admin Building in ISI Campus Delhi Centre New Delhi-110016.

The Head ISI Delhi Centre , 7 Shahid Jeet Singh Marg , opposite Katwaria Sarai, New Delhi 110016 , invites item rate was sealed tenders on behalf of I.S.I Delhi Centre for the above work from the vendors having experience in Govt./PSU/ etc. organisation in similar type of works..

1. Eligibility Conditions:-

- a. The intending Tenderers shall submit the proof of **GST registration certificates** and list of works completed along-with any one copy of certificates/ testimonials of their satisfactory completion from the department concerned obtained from an officer not below the rank of Executive Engineer-in-charge of the work, while submitting the tender.
- b. Tenders should be submitted PAN No.
- c. Relevant Exp. Document in GOVT. Deptt should be submitted.
- d. Taxes will be deducted as per the norms of Govt. Other taxes and Charges should be paid by the contractor himself.
- e. Tenders, which should always be placed in sealed envelope, in the manner detailed at para 2 below, will be received by **the OSD , ISI Delhi Centre , New Delhi-16 up to 15.00 Hrs. on 13/06/2018** and will be opened by him or his authorized representative in his office on the same day at 15.30 Hrs. After opening the main envelope 3, the envelope 1 containing the **GST** Registration Document/ works completed along-with copy of certificates /PAN No./ etc. (**as refer as Technical bid**) applicable and eligibility credentials shall be opened first. The envelope 2 containing tender shall be opened only for those tenderers whose **BOQ** (Bill of Quantities) (**refer as Financial bid**) found in order.

2. Submission of tender : -

Tender shall be submitted in following manner:

2.1 In case the tender document is down loaded from ISI Delhi website -

2.1.1 "the envelope 1 containing the GST Registration Document/ works completed along-with any copy of certificates /PAN No./ etc. shall be placed in sealed envelope-1 marked "**as Technical bid**".

2.1.2 The "**BOQ** (Bill of Quantities) (**refer as Financial bid**)" shall be placed in sealed envelope-2 and will be superscripted as "**Financial bid**".


2.1.3 The sealed envelope no. 1 & 2 as above containing "Technical bid", and the "Financial bid" shall be placed in another sealed envelope -3.

2.1.4 All the three envelopes shall be superscripted with following data on it.

- (xi) Name of work
- (xii) Name of tenderer


3. Terms and Condition

- a. Tenderer first visited the site before submitting the tender.
- b. The work has to be executed strictly as per CPWD specification/Norms.
- c. Payments shall be made based on the satisfactory actual work done and based on the actual measurement, after deduction of 5%, which shall be kept as security to cover the defects liability period of six month from the date of completion. During this period any defects are found the same shall be got rectified immediately by you.
- d. The payment should be made based on the Malaba removing out from the campus.
- e. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assigning any reason.


Sd/- 29/5/2018

On behalf of ISI Delhi Centre,

Signature of bidder with seal & Date



Notice Inviting Tender

NIT No- D / ISI /Civil Work /2018-19 / 355

Dated 28/05/2018

Name of work : Providing and Fixing of Existing Window AC with Renewal wooden frame in Faculty Building/GH/Admin Building in ISI Campus Delhi Centre New Delhi-110016.

FINANCIAL BID


Sr No	Description of item of work	Unit	Qty	Rate	Amount
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).				
	Sal wood	cum	0.652		
2	Providing and fixing plywood 6 mm thick, plain normal non-decorative. Make-Century/Royal/Challenge/Merino/Greenlam/Duro/Amul	sqm	48.3		
3	Taking out existing AC, with frame taking all precaution, without damaging AC part and keep in safe side including all lead and lift. (As per direction of Engineer- In charge (electrical)	Each	69		
4	Refixing of Existing AC taking all precaution, without damaging AC part and keep in after preparation of frame work. including all lead and lift. (As per direction of Engineer- Incharge (electrical)	Each	69		
	Total(inclusive taxes)				
	extra taxes if any				
	Total(inclusive taxes)				
	Rebate/discount if any				

	Grand Total (inclusive taxes)			
--	-------------------------------	--	--	--

Kamishur Alam
sd

on behalf of ISI Delhi Centre

Signature of bidder with seal & Date



Indian Statistical Institute
Delhi Centre
Notice Inviting Tender

NIT No- D / ISI /Civil Work /2018-19 / 356

Dated 28/05/2018

Name of work : Painting works and Raising of over head tanks in Electrical Substation in ISI Campus Delhi Centre New Delhi-110016.

The Head ISI Delhi Centre , 7 Shahid Jeet Singh Marg , opposite Katwaria Sarai, New Delhi 110016 , invites item rate sealed tenders on behalf of I.S.I Delhi Centre for the above work from the vendors having experience in Govt./PSU/ etc. organisation in similar type of works..

1. Eligibility Conditions:-

- a. The intending Tenderers shall submit the proof of **GST registration certificates** and list of works completed along-with any one copy of certificates/ testimonials of their satisfactory completion from the department concerned obtained from an officer not below the rank of Executive Engineer-in-charge of the work, while submitting the tender.
- b. Tenders should be submitted PAN No.
- c. Relevant Exp. Document in GOVT. Deptt should be submitted.
- d. Taxes will be deducted as per the norms of Govt. Other taxes and Charges should be paid by the contractor himself.
- e. Tenders, which should always be placed in sealed envelope, in the manner detailed at para 2 below, will be received by **the OSD , ISI Delhi Centre , New Delhi-16 up to 15.00 Hrs. on 14/06/2018** and will be opened by him or his authorized representative in his office on the same day at 15.30 Hrs. After opening the main envelope 3, the envelope 1 containing the **GST** Registration Document/ works completed along-with copy of certificates /PAN No./ etc. (**as refer as Technical bid**) applicable and eligibility credentials shall be opened first. The envelope 2 containing tender shall be opened only for those tenderers whose **BOQ** (Bill of Quantities) (**refer as Financial bid**) found in order.

2. Submission of tender : -

Tender shall be submitted in following manner:

2.1 In case the tender document is down loaded from ISI Delhi website -

2.1.1 "the envelope 1 containing the GST Registration Document/ works completed along-with any copy of certificates /PAN No./ etc. shall be placed in sealed envelope-1 marked "**as Technical bid**".

2.1.2 The "**BOQ** (Bill of Quantities) (**refer as Financial bid**)" shall be placed in sealed envelope-2 and will be superscripted as "**Financial bid**".


2.1.3 The sealed envelope no. 1 & 2 as above containing "Technical bid", and the "Financial bid" shall be placed in another sealed envelope -3.

2.1.4 All the three envelopes shall be superscripted with following data on it.

- i.) Name of work
- ii.) Name of tenderer

3. Terms and Condition


- a. Tenderer first visited the site before submitting the tender.
- b. The work has to be executed strictly as per CPWD specification/Norms.
- c. Payments shall be made based on the satisfactory actual work done and based on the actual measurement, after deduction of 5%, which shall be kept as security to cover the defects liability period of six month from the date of completion. During this period any defects are found the same shall be got rectified immediately by you.
- d. The payment should be made based on the Malaba removing out from the campus.
- e. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assigning any reason.



Sd/-

On behalf of ISI Delhi Centre,

Signature of bidder with seal & Date



Notice Inviting Tender

NIT No- D / ISI /Civil Work /2018-19 / 356

Dated 28/05/2018

Name of work : Painting works and Raising of over head tanks in Electrical Substation in ISI Campus Delhi Centre New Delhi-110016.


FINANCIAL BID

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	839.24		
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
	Old work (one or more coats)	sqm	839.24		
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the lastered wall surface to prepare the surface even and smooth complete.				
	same as item 1-40% paid only(AS PER TOTAL)	sqm	335.7		
4	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	One or more coats on old work	sqm	123.35		
	15.0 DEMANTLING AND DEMOLISHING				
5	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.				
	In cement mortar	cum	1.152		

6	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.	sqm	9.25		
7	Grading roof for water proofing treatment with				
	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	1.152		
8	12 mm cement plaster finished with a floating coat of neat cement of mix :				
	1:3 (1 cement: 3 fine sand)	sqm	9.25		
9	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	cum	0.144		
10	Malaba Removing out and dump approved municipal ground	l/s	1job		
11	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design :				
	In 75x75 mm deep chase	meter	10		
12	Raking out joints in lime or cement mortar and preparing the surface for repointing or replastering, including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	9.86		
13	Flush pointing with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement for flat tile bricks on top of mud phaska :				
	With modular brick tiles	sqm	9.86		

14	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	8.876		
15	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	sqm	8.876		
16	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.				
	Circular tank	ltr	1000		
17	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	15 mm to 40 mm nominal bore	meter	12		
18	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works L-50 x 50 x 6 mm =(1 mtr = 4.111kg/mtr)/steel plate-5 mm thick	kg	519.41		
	plumbing work				
19	Providing and Fixing of GI Tank Nipple -3/4"	each	3		
20	providing and fixing of GI Union-3/4"	each	3		
21	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) -3/4"				
	20 mm nominal bore	each	2		
22	Providing and Fixing of GI socket -3/4"	each	4		
23	Providing and Fixing of GI elbow -3/4"	each	5		
24	Providing and Fixing of GI Tee -3/4"	each	3		
25	Providing and Fixing of GI Nipple 1-6" -3/4"	each	2		

26	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall :				
	20 mm dia nominal bore(JINDAL/HISAR/140	meter	13		
27	Providing and Fixing of GI elbow -3/4" x 1/2"	each	2		
28	providing and fixing GI Nipple -1/2"-- L-4"	each	2		
29	providing and fixing GI Nipple -3/4"-- L-4"	each	2		
30	providing and fixing GI Nipple -3/4"-- L-6"	each	2		
31	providing and fixing GI Nipple -3/4"-- L-3"	each	2		
32	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :(Prayag)				
	20 mm nominal bore	each	1		
	concreting work				
33	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	0.86		
	Total(inclusive taxes)				
	extra taxes if any				
	Total(inclusive taxes)				
	Rebate/discount if any				
	Grand Total (inclusive taxes)				


 sd
 on behalf of ISI Delhi Centre

Signature of bidder with seal & Date