



INDIAN STATISTICAL INSTITUTE, DELHI CENTRE
7 S.J.S MARG, KATWARIA SARAI
NEW DELHI 110016
NOTICE INVITING e-TENDER

NIT No- D / ISI /Civil Work /2018-19 / 405

Dated: - 04/01/2019

Indian Statistical Institute, Delhi Centre, invites on line tenders item rate on prescribed tender documents under single bid system for the work of "Renovation works of toilet/bathrooms and other Civil Work in qtrs.. of A-13 " in ISI Campus Delhi Centre, New Delhi-110016" from reputed contractors and who fulfill other eligibility criteria of tender document. Tender notice available on www.eprocure.gov.in/www.isid.ac.in under Administrative Announcements & Tenders.

1	Name of officer and office inviting tender	Dy. Chief Executive , Delhi centre, Indian Statistical Institute, Delhi Centre, 7 S.J.S Marg ,Katwaria Sarai, New Delhi-110016
2	Name of the work	Renovation works of toilet/bathrooms and other Civil Work in qtrs.. of A-13
3	Bidding document No	Tender No. D / ISI /Civil Work /2018-19 /405
4	Estimated cost put to the tender	Rs. 2,30,247/- (Rupees Two Lacs Thirty Thousand & Two Hundred Fourty Seven /-)
5	Period of Work	One Month
6	Cost of tender documents	NIL

7	Earnest money deposit (EMD)	<p>Rs. 4600/- (Rupees Four Thousands & Six Hundred Only) Demand Draft (DD) only</p> <p>In favour of "Indian Statistical Institute" payable at New Delhi.</p> <p>(DD to be submitted Addressed to Head, Indian Statistical Institute, Delhi Centre, New Delhi 110016 either in person or through speed post. Earnest money received after the closing date and time of tender will not be entertained. The Institute will not be responsible for any postal delay.</p>
8	Tender mode	On line (Through cppp portal)
9	Date & Time of uploading NIT and other documents	04.01.2019- 6.00 PM

10	Downloading of Tender Documents from website of www.eprocure.gov.in	05.01.2019 (after 10:00 AM onwards)
11	Last Date & Time of on line submission of tender	24.01.2019 (3:00 PM)
12	Opening of tender	25/01/2019 at 03.30 PM (IST)
13	Documents to be attached along with the tender	<p>1) Work Experience Certificate</p> <p>2) Copy of PAN No. and GSTIN certificate</p>

Terms and Condition: -

14- Eligibility Criteria :

The bidder must fulfil the following eligibility criteria and should submit the following document;

1. The bidder should fulfil the criteria of satisfactory execution of at least 1 similar type's works and should submit the works experience certificate.
2. The bidders should submit the related document in support of above works issued by respective departments.
3. The bidders should submit valid PAN No. GST No.
4. The rates for the above work shall be valid for one year and during this period; the work will be carried out as per the need basis or direction as per the institute authorities.
5. Before tendering, the bidder shall inspect the site to fully acquaint himself.
6. Payments shall be made based on the satisfactory actual work done and based on the actual measurement, after deduction of 5%, which shall be kept as security to cover the defects liability for a period of six month from the date of completion. During this period, any defect is found the same shall be got rectified immediately by you. No extra payment will be made.
7. All Successful/unsuccessful bidders EMD will be return after verification of tender/document/process complete.
8. The works shall be strictly carried out as per the latest CPWD specification of work and works manual under the supervision of Engineer Civil A.
9. The ISI Delhi Centre reserves the right to reject the tender process at any stage without assigning any reason.
10. The quoted rates shall be inclusive of all taxes and charges as applicable.
11. Any loss/ damaged/ theft caused to the public property/ ISI Delhi Centre / manpower engaged shall be sole responsibility of the agency.
12. The contractor shall be responsible for their good character, all damaged done to the existing structure shall be made good by the contractor at his own risk and cost.
13. ISI Delhi Centre shall not be responsible for any injury or loss any worker of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of the life shall be the sole responsibility of the contractor. The contractor is solely responsible for any damage or injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to ISI Delhi Centre.
14. After finishing of work Malaba may be removing out at own cost.
15. The tender document can be downloaded from website. Corrigendum, if any would appear on the www.eprocure.gov.in / www.isid.ac.in.
16. The tender document can be downloaded from website. Corrigendum, if any would appear on the www.eprocure.gov.in / www.isid.ac.in. ISI Delhi Centre reserves the right to accept or reject any or all tenders in part or full without assigning any reason thereof.
17. Tenders / offers sent by fax / email will not be considered and would be rejected.
18. Any incomplete of paper found in tender document, the tender document may be summarily rejected.


Dy. Chief Executive, Delhi Centre

FINANCIAL BID

Subject: - Renovation works of toilet/bathrooms and other Civil Work in qtrs. of A-13 in ISI Campus Delhi Centre New Delhi-110016.

Sr No.	Description of Work	Unit	Qty	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	68.304		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
	For thickness of tiles above 25 mm and up to 40 mm	sqm	10.362		
3	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	68.304		
4	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	sqm	10.362		
5	CEMENT PLASTER (IN COARSE SAND)				
	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 coarse sand)	sqm	68.304		
6	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	15 mm to 40 mm nominal bore	meter	10.53		

7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. (Astral Make)				
	Concealed work, including cutting chases and making good the walls etc.				
	20 mm nominal outer dia Pipes	meter	64.45		
8	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
	15mm nominal bore	each	12		
9	Providing and Fixing 2 in 1 CP Brass Bib Cock approved quality conforming to IS Standard.	each	3		
10	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.				
	15 mm nominal bore	each	8		
11	Providing and Fixing CP Brass Wall mixture approved quality conforming to IS Standard.	each	1		
12	Providing and Fixing CP Brass Concealed -1/2" approved quality conforming to IS Standard.	each	4		
13	Providing and Fixing Telephonic hand shower 70 mm (3" dia with wall hook and 1.5 mtr hose pipe , approved quality conforming to IS standards	each	1		
14	Providing and Fixing Overhead shower 100 mm (4" dia with single flow with shower arm-6" Long approved quality conforming to IS standards	each	1		
15	Providing and fixing plasticised PVC connection pipe with brass unions :				
	45 cm length				
	15 mm nominal bore	each	7		
16	Providing and Fixing of CP brass Central Hole Basin Mixture-Single Leaver- Central Hole --approved quality conforming to IS Standard.	each	2		
17	Providing and Fixing CP Brass Health Faucet ABS Body with wall hook and 1 meter PVC hose pipe ,approved quality conforming to IS standards	each	2		
18	Providing and Fixing CP Paper holder with flap guard	each	2		

19	Providing and Fixing of CP Towel Rail 600 mm long	each	2		
20	Providing and Fixing of CP Towel Ring 7" dia	each	2		
21	Providing and Fixing of CP soap dish	each	2		
22	Providing and Fixing CP JALI -4"	each	4		
23	Providing and Fixing CP JALI -4" Hole	each	3		
24	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				
	Flexible pipe				
	32 mm dia	each	2		
25	Providing and fixing Stainless Steel A ISI : 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :				
	Kitchen sink with drain board				
	510x1040 mm bowl depth 250 mm	each	1		
26	Providing and Fixing Galvanised M.S. Wire gauze with 0.63 mm dia wire and 1.4 mm aperture on both sides(Removing old GI wire, complete as per direction of Engineer- in-charge	sqm	12.119		
27	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	0.1		
28	Providing and fixing to existing door frames.				
	30 mm thick Fiberglass Reinforced Plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF)/ Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856, complete as per direction of Engineer- in-charge.	sqm	3.78		
29	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :	each	4		
30	Providing and fixing aluminium tower bolts, ISI				

	marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	300x10 mm	each	2		
31	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :				
	300x16 mm	each	2		
32	Providing and Fixing of plywood of 12 mm non decorative and dismantling of old plywood including complete complete as per direction of Engineer-in-charge.	sqm	15.889		
33	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade				
	One or more coats on old work	sqm	165.414		
34	Providing and Laying polishing on wood work (one or more coat).as per existing grain size complete as per direction of Engineer- in-charge	sqm	88.05		
35	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :				
	Of area 3 sq. metres and below	each	2		
36	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In- Charge.	sqm	3.42		
37	Floor polishing on masonry or concrete floors with wax polish of approved brand and manufacture.	sqm	101.307		
38	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete :				
	25 mm dia	meter	9.975		
39	Malaba removing out of the campus	1 job	L/S		

	Total (inclusive taxes GST)				
	Extra GST 18%				
	Total (inclusive taxes GST)				
	Rebate /Discount if any				
	Total (inclusive taxes GST)				



sd
Dy. Chief Executive, Delhi Centre

Signature of bidder with seal & Date