


भारतीय सांख्यिकी संस्थान  
दिल्ली केंद्र



ग्राम स्टैटिस्टिक्स, नई दिल्ली

फोन : 41493951

फैक्स : 41493981

ईमेल : [headdc@isid.ac.in](mailto:headdc@isid.ac.in)

7, एस जे एस, सनसनवाल मार्ग,  
कुतुब होटल के पास  
कटवरिया सराय नई दिल्ली

निविदा आमंत्रित सूचना

Tender Notice

निविदा नं. D /ISI /CIVIL WORK /2018 -2019 / 390

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 24/09/2018 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

NAME OF WORK :-Repairing of plasters and Painting works & changed doors of toilet/bathroom & kitchen touchup/painting works Flat No. D-22/18 in ISI campus , Delhi centre, New Delhi.					
Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Removing dry or oil bound distemper, water proffing cement paint and the like by scrapping, sand preparing and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	109.18		
2	Providing and applying white cement based putty of average thickness 1 mm , of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete				
	40% of item no. 1	sqm	43.67		
3	Distemping with oil bound washable distemper of approved brand and manufacture to given an even shade.				
	old work ( one or more coats)	sqm	109.18		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	91.69		
	CEMENT PLASTER (IN COARSE SAND				
5	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 coarse sand)	sqm	72.46		
6	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	l/s	1 job		
7	Providing and fixing to existing door frames.				
	30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames.	sqm	5.88		

8	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :				
	300x16 mm	each	4		
9	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	300x10 mm	each	4		
10	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :				
	Of area 3 sq. metres and below	each	4		
	for 3 flats				
11	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	each	1		
12	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge.				
	With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	18.003		
	18.0 WATER SUPPLY				
13	Providing and fixing G.I. pipes complete with G.I. fittings and lamps, i/c cutting and making good the walls etc.				
	Internal work - Exposed on wall				
	<b>15 mm dia nominal bore</b>	meter	28.64		
14	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	Two or more coats on old work	sqm	22.93		
15	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.				
	Twin rubber stopper	each	8		
16	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete :				
	300x16 mm	each	1		
17	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				

	15 mm to 40 mm nominal bore	meter	28.64		
18	Welding of hinges (welding work)including/carrriage/loading/uploading of machine including in all complete as per direction of engineer incharge	l/s	1 job		
	Total(inclusive taxes)				
	Extra taxes(GST) if any				
	Total(inclusive taxes(GST)				
	Rebate/discount if any				
	Grand Total (inclusive taxesGST)				

**Terms and Condition: -**

**1. Eligibility Criteria :**

1. The bidder must fulfil the following eligibility criteria and should submit the following document;
  - i) The bidder should fulfil the criteria of satisfactory execution of at least 1 similar type's works and should submit the works experience certificate.
  - ii) The bidders should submit the related document in support of above works issued by respective departments.
  - iii) **The bidders should submit valid PAN No. GST No.**
2. Before tendering, the bidder shall inspect the site to fully acquaint himself.
3. Payment shall be made based on the satisfactory actual work done, and based on the actual measurement, after deduction of 5% which shall be kept as a security to cover the defects liability for a period of six month from the completion work. During this period, any defects is found the same shall be got rectified immediately by you. No extra payment will be made.
4. The works shall be strictly carried out as per the latest CPWD specification of work and works manual under the supervision of Engineer Civil A.
5. The ISI Delhi Centre reserves the right to reject the tender process at any stage without assigning any reason.
6. The quoted rates shall be inclusive of all taxes and charges as applicable.
7. Any loss/ damaged/ theft caused to the public property/ ISI Delhi Centre / manpower engaged shall be sole responsibility of the agency.
8. The contractor shall be responsible for their good character, all damaged done to the existing structure shall be made good by the contractor at his own risk and cost.
9. ISI Delhi Centre shall not be responsible for any injury of loss any worker of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of the life shall be the sole responsibility of the contractor. The contractor is solely responsible for any damage or injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to ISI Delhi Centre.
10. After finishing of work Malaba may be removing out at own cost. Your payment liable to malaba removing out of the Campus.
11. The tender document can be downloaded from website. Corrigendum, if any would appear on the [www.isid.ac.in](http://www.isid.ac.in).
12. ISI Delhi Centre reserves the right to accept or reject any or all tenders in part or full without assigning any reason thereof.
13. No extra cartage will be paid for delievery of the material in the campus.
14. No Advance Payment will be made.
15. if found the document not enclosed( as per given above stated) at the time of opening of tender the tender may be rejected.

*agbhatt*

Head, Delhi Centre

Bidder Signature with Date