

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र



7, एस जे एस, सनसनवाल मार्ग,
कुतुब होटल के पास
कटवरिया सराय नई दिल्ली
110016

ग्राम स्टैटिस्टिका, नई दिल्ली
फ़ोन : 41493983
फैक्स : 41493981
ईमेल : srinivas@isid.ac.in

निविदा आमंत्रित सूचना
Tender Notice

निविदा नं. D /ISI /CIVIL WORK /2017 -2018 / 378

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण (quotation) तारीख 08/08/2018 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Name of work :- Painting and other civil work in B-2 in ISI Campus Delhi Centre New Delhi-110016

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches	sqm	273.732		
2	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	sqm	273.732		
3	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :				
	New work (two or more coats) over and including water thinnable priming coat with cement primer	sqm	273.732		
4	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete.				
	With 2nd class teak wood beading 62X19 mm	sqm	7.56		
	FRAMES AND TRUSSES				
5	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & ength (hold fast lugs or dash fastener shall be paid for separately).				
	Sal wood	cum	0.010		
	STAINLESS STEEL FITTINGS				
6	Providing and fixing IS : 12817 marked stainless steel butt hinges (heavy weight) with stainless steel screws etc. complete :				
	100x60x2.50 mm	each	3		
7	Iron Grill Cutting- size of -0.670 x 2.100 complete as per direction of the Engineer-in-Charge. Including and lead and lift	L/S	1 JOB		
	C.P.V.C. PIPES(Astral make)				

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.				
	Concealed work, including cutting chases and making good the walls etc.				
	20 mm nominal outer dia Pipes	Meter	19.47		
9	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete :				
	White solid plastic seat with lid	each	2		
10	Dismantling G.I./CPVC pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	15 mm to 40 mm nominal bore	meter	15.47		
11	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	17.28		
	CERAMIC GLAZED TILES(Kajariya/Orient)				
12	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	17.28		
13	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :				
	Of area beyond 3 sq. metres	each	1		
14	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :				
	Of area beyond 3 sq. metres	each	4		
15	Providing and fixing to existing door frames.				

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
	30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames.	sqm	3.36		
16	Providing and fixing cp towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.				
	600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	each	1		
17	Providing and fixing glass shelf 440 mm long, 124 mm width and 36 mm height of approved quality and colour, weighing not less than 300 gms.	each	1		
18	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :				
	Rectangular shape 453x357 mm	each	2		
	small/big toilet				
19	Providing and fixing C.P. brass overhead shower 95 mm (4") dia with single flow and shower arm :	each	1		
20	Providing and fixing uplasticised PVC connection pipe with brass unions :				
	45 cm length				
	15 mm nominal bore	each	4		
21	Providing and Fixing of cp brass sink mixture centre hole -single lever ISI Mark heavy duty	each	1		
22	Providing and fixing ss kitchen sink single bowl 1.0 mm thick 304 grade with drain board of required size(1.300 x 0.460 x 8") and shape ISI Mark heavy duty	each	1		
23	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				
	Flexible pipe				
	40 mm dia	each	2		
24	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
	15mm nominal bore	each	5		
25	Providing and fixing C.P. brass 2 in 1 bib cock points of approved quality	each	1		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
26	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.				
	15 mm nominal bore	each	3		
27	Providing and Fixing of cp brass consealed -15 mm-full set-Heavy duty	each	2		
28	Providing and fixing C.P. brass piller Cock of approved quality				
	15 mm nominal bore	each	2		
29	Providing and Fixingof heath faucet ABS body with wall hook and 1 meter cp PVC hose pipe- heavy duty ISI Mark	each	1		
30	p/f pf Upvc pipe of 1.25" (prince make) ISI Mark	Meter	2		
31	p/f pvc bend 1.25" x 1.25 " (prince/prakash make) ISI Mark	each	3		
32	Cutting/chasing up to 75 x 75 mm in concrete/R.C.C. floors and roofs for laying drain pipe etc. and repairing the cutting/chasing after insertion of drain pipe etc. with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete so as to make it leak proof.				
	75 mm dia	meter	2		
33	p/f of GI -Tee-3/4" x 1/2 " (Unik Make)	each	1		
34	p/f of Union -3/4" (Unik Make)	Each	1		
35	p/f GI Nipple- 3/4"-L-4"X 2	each	2		
36	cpvc fitting -brass elbw-1/2 x 3/4 " (Astral Make)	each	1		
37	upvc plain elbow-3/4 " (prince/prakash make)	each	1		
38	p/f MT- 1/2" X 3/4 (Astral Make)	each	1		
39	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
	15mm nominal bore	each	6		
40	providing and fixing of plywood 18 mm thick (Century Plywood)	sqm	6.35		
	Applying priming coat:				
41	With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	sqm	2.75		
42	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and anufacture	sqm	6.354		
43	Providing and fixing 2nd class teak wood lipping/ moulded beading or taj beading of size 18X5 mm fixed with wooden adhesive of approved quality and screws/ nails on the edges of the Pre-laminated particle board as per direction of Engineer-in-charge.	meter	40.84		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
44	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	3		
45	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	sqm	1.995		
46	Floor polishing on masonry or concrete floors with wax polish of approved brand and manufacture.	sqm	56.484		
47	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In- Charge.	sqm	9.583		
48	Painting (two or more coats) on rain water, soil, waste and vent pipes and fittings with aluminium paint of approved brand and manufacture over a priming coat of ready mixed zinc chromate yellow primer on new work :	Meter	12		
	100 mm diameter pipes				
49	Providing and fixing frosted glass with removing of old glass	sqm	0.5625		
50	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete :				
	20 mm dia	meter	5.1		
51	Finishing walls with textured exterior paint of required shade :				
	Old work (Two or more coats on existing cement paint surface applied @ 3.28 ltr/10 sqm.	sqm	8.9		
52	Malaba removing outside campus	l/s	1 job		
53	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws				
	Twin rubber stopper	each	6		
	Total(inclusive taxes)				
	Extra taxes(GST) if any				
	Total(inclusive taxes(GST)				
	Rebate/discount if any				
	Grand Total (inclusive taxesGST)				

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
--------	-----------------------------	------	-----	------	--------

Terms and Condition: -

1. Eligibility Criteria :

The bidder must fulfil the following eligibility criteria and should submit the following document;

i) The bidder should fulfil the criteria of satisfactory execution of at least 3 similar type's works and should submit the works experience certificate.

ii) The bidders should submit the related document in support of above works issued by respective departments.

iii) The bidders should submit valid PAN No. GST No.

2. Before tendering, the bidder shall inspect the site to fully acquaint himself.

3. Payment shall be made based on the satisfactory actual work done, and based on the actual measurement, after deduction of 5% which shall be kept as a security to cover the defects liability for a period of six month from the completion work. During this period, any defects is found the same shall be got rectified immediately by you. No extra payment will be made.

4. The works shall be strictly carried out as per the latest CPWD specification of work and works manual under the supervision of Engineer Civil A.

5. The ISI Delhi Centre reserves the right to reject the tender process at any stage without assigning any reason.

6. The quoted rates shall be inclusive of all taxes and charges as applicable.

7. Any loss/ damaged/ theft caused to the public property/ ISI Delhi Centre / manpower engaged shall be sole responsibility of the agency.

8. The contractor shall be responsible for their good character, all damaged done to the existing structure shall be made good by the contractor at his own risk and cost.

9. ISI Delhi Centre shall not be responsible for any injury of loss any worker of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of the life shall be the sole responsibility of the contractor. The contractor is solely responsible for any damage or injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to ISI Delhi Centre.

10. After finishing of work Malaba may be removing out at own cost. Your payment liable to malaba removing out of the Campus.

11. The tender document can be downloaded from website. Corrigendum, if any would appear on the www.isid.ac.in.

12. ISI Delhi Centre reserves the right to accept or reject any or all tenders in part or full without assigning any reason thereof.

13.No extra cartage will be paid for delievery of the material in the campus.

14. No Advance Payment will be made.

agbhatt

Head, Delhi Centre

Bidder Sinature with Date