

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र

ग्राम स्टैटिस्टिका , नई दिल्ली
फोन : 41493984
फैक्स : 41493981
ईमेल : kalam@isid.ac.in



7, एस जे एस, सनसनवाल मार्ग,
कुतुब होटल के पास
कटवरिया सराय नई दिल्ली

निविदा आमंत्रित सूचना

Tender Notice

निविदा नं. D /ISI /CIVIL WORK /2017 -2018 / 310

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 04/09/2017 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Providing and Fixing of Plumbing CI Pipelines and and waterproofing work in old hostel room no. 315-316					
Sr No.	Description of item of work	Unit	Qty	Rate	Amount
DISMANTLING AND DEMOLISHING					
1	Dismantling tile work in floors and roofs laid in cement mortar Including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm	sqm	4.998		
2	Dismantling old C.I. pipes including excavation and refilling trenches after taking out the pipes, breaking lead caulked joints, melting of lead and making into blocks, including stacking of pipes at site lead up to 50 metre:	meter	6.3		
3	Labour for cutting C.I. pipe with steel saw. 100 mm diameter C.I. pipe	each cut	3		
4	Taking out of flushing cistern of all types (C.I./PVC/Vitrious China)/ indian/european wc/washbasin including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	3		
5	Refixing of flushing cistern of all types (C.I./PVC/Vitrious China)/ indian/european wc/washbasin etc. wc/cistern/wash basin	each	3		
6	Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 :				
	4"	meter	1.5		
	3"	meter	1.8		
7	providing and fixing of CI P- Trap- 4" to 3"	each	1		
8	Providing and Fixing of upvc bend 65 mm 90 degree	each	2		
9	providing and fixing of upvc pipe 65 mm	meter	3		
10	providing and fixing cp jali drain floor-3"	each	2		
	4"	each	2		
11	Providing/supplying lead caulked joints to spun iron or C.I. pipes and specials, including testing of joints including the cost of pig lead :				
	100 mm diameter pipe	each	5		
TILE FLOORING					

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
12	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	sqm	4.998		
	REPAIRS TO BUILDING				
13	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-charge.				
	With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	8.998		
	FINISHING				
14	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	15.4198		
15	Distempering with dry distemper of approved brand and manufacture (one or more coats) and of required shade on old work to give an even shade.	sqm	15.4198		
	Old work (one or more coats)				
16	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.				
	40 % of painting	sqm	6.167		
17	Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying:				
	(a) after surface preparation, first layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours.				
	(b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.	sqm	4.998		
	Total(inclusive taxes)				
	extra taxes if any				
	Total(inclusive taxes)				
	Rebate/discount if any				
	Grand Total (inclusive taxes)				

वि.जी. चव्हाण

अभियंता सिविल ' ए '

4
दस्तावेज तालिका
27/9/2017
ओएसडी

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
--------	-----------------------------	------	-----	------	--------

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "पैन नम्बर " "(जीएसटी)-" नं. लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
9. सिक्क्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिम्मेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assigning any reason.
13. (जीएसटी- नं.) GST - No. is a mandatory from of 1ST JULY 2017. Please enclosed GST Registration document.
14. For any clarification OSD may be contacted
15. The Quotationer Should be in PWD/ CPWD Registered. The Registration Document enclosing is must.

प्रति :-

1. सूचना पलट
2. वेब स्थल आई एस आई दिल्ली केन्द्र