

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र

ग्राम स्टैटिस्टिका, नई दिल्ली

फ़ोन : 41493984

फैक्स : 41493981

ईमेल : kalam@isid.ac.in



7, एस जे एस, सनसनवाल मार्ग,
कुतुब होटल के पास
कटवरिया सराय
नई दिल्ली

निविदा आमंत्रित सूचना


निविदा नं. D/ISI/CIVIL WORK/2016-2017/251


मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 23/12/2016 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

NAME OF WORK :-Water Proofing work in D-4- FLAT in ISI campus , Delhi centre, New Delhi.

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.				
	patch 1	sqm	21.17		
2	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)				
	patch 1	cum	1.588		
	CEMENT PLASTER WITH A FLOATING COAT OF NEAT CEMENT				
3	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:3 (1 cement: 3 fine sand)	sqm	21.17		
	15.0 DISMANTLING AND DEMOLISHING				
4	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	cum	1.588		
5	MALABA REMOVING	l/s	1		
6	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design :				
	In 75x75 mm deep chase	meter	20.3		
7	Removing dry or oil bound distemper, water proffing cement paint and the like by scrapping, sand preparing and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	21.95		

8	Providing and applying white cement based putty of average thickness 1 mm , of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	sqm	21.95		
9	Distemping with oil bound washable distemper of approved brand and manufacture to given an even shade.				
	old work (one or more coats)	sqm	21.95		
	Total (inclusive taxes)			Total	


अभियंता सिविल 'अ'


ओएसडी

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या क्रियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.

प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र