

Date: 21/08/2013


INDIAN STATISTICAL INSTITUTE
DELHI CENTRE

GramSTATISTICA, NEW DELHI :

Phone: 91-11-41493980

Fax: 91-11-41493981

Email : sethi@isid.ac.in



7, SJS SANSANWAL MARG

NEAR QUTAB HOTEL

KATAWARIA, SARAI, NEW DELHI-

110016(INDIA)

No.D/ISI/DCE/2013-14/ 126

Date:-21/08/2013


QUOTATION

Sealed Quotations are invited so as to reach this office on or before 23/08/2013 and shall be opened on the same date at 3.00PM in front of whosoever present.

Name of Work:- Kota Stone flooring in front of Guest House.

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Earth work in surface excavation not exceeding 30 cm in depth as well as 10 sqm on plain including disposal of excavated earth upto 50 mtr and lift upto 1.5 mtr disposed soil to be levelled and neatly dressed.				
	All kinds of soil	sqm	33.18		
2	laying spreading and compacting water bound macadam sub base with brick aggregate and binding material, earth etc.,including screeing, sorting and spreading to template and consolodiation with light power road -roller etc.,complete				
	over burnt(jhama)brick aggregate 120 mm 40 mm	cum	4.976		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering-All works upto plinth level				
	(1:4:8)	cum	3.318		
4	Kota stone slab flooring over 20 mm (avg) thick base laid over and jointed with grey cement slurrey mixed with pigment to match shade of the slab, including rubbing and polishing complete with the base of cement mortor(1:4)				
	25 mm thick	sqm	33.18		


Engineer Civil A


QSD

Note:-

1. The Quotationer must visit the site before giving the offer.
2. The work will be carried out as per latest CPWD Specification, under the supervision of Engineer(civil)
3. The time of completion will be 10 days from the date of issue of work order.
4. The Quotationer must submit the paper (along with quotation) of Registration of DVAT, PAN NO. TIN NO. ETC.