


भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र

ग्राम स्टाटिस्टिक्स , नई दिल्ली
फ़ोन : 41493984
फैक्स : 41493981
ईमेल : kalam@isid.ac.in



7, एस जे एस, सनसनवाल मार्ग,
कुतुब होटल के पास
कटवरिया सराय नई दिल्ली

निविदा आमंत्रित सूचना

Tender Notice

निविदा नं. D /ISI /CIVIL WORK /2017 -2018 / 339

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 15/03/2018 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

NAME OF WORK :- Preparation of shed of cycle stand with iron support/structure /shading of pc sheet/and parking tile work

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
	Hot finished welded type tubes				
	support				
	sq tube 40 x 40 x 4.0 mm				
	weight = 4.2 kg/mtr.	kg	388.08		
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works				
	f-1				
	12 mm dia =0.88kg/mtr-----f-2	kg	18.38		
3	Earth work in excavation by mechanical means (Hydraulic cavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
	All kinds of soil	cum	0.54		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	"1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	cum	0.54		
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete				
	40 mm thick with 20 mm nominal size stone aggregate	sqm	17.632		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
6	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).				
	Medium shade pigment using 50% white cement 50% Grey cement	sqm	17.632		
7	PC Lite Hollow / Multiwall Sheets				
	Providing and Laying of PC Lite Hollow / Multiwall Sheets				
	Standard Colors – Clear, Lake ue, Green, Bronze, Opal, Metallic Grey , Orange & Blue.				
	Standard Thickness – 10	sqm	36.48		
8	Providing and fixing carbon steel galvanised (minimum coating 5 micron) dash fastener of 10 mm dia double threaded 6.8 grade (yield strength 480 N/mm2), counter sunk head, comprising of 10 m dia polyamide PA 6 grade sleeve, including drilling of hole in frame , concrete/ masonry, etc. as per direction of Engineer-in-charge.				
	10 x 60 mm	each	36		
9	Malaba removing outside campus and dump in approved muncipal place with prior to permission etc.	l/s	1		
	Total(inclusive taxes)				
	extra taxes if any				
	Total(inclusive taxes)				
	Rebate/discount if any				
	Grand Total (inclusive taxes)				

B. Chavan

अभियंता सिविल ' ए '

अभिषेक शर्मा
ओएसडी
27/2/2018

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "पैन नम्बर " "(जीएसटी)-" नं. लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
9. सिक्चोरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
--------	-----------------------------	------	-----	------	--------

11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिम्मेदार नहीं रहेगी.

12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.

13. (जीएसटी- नं.) GST - No. is a mandatary from of 1ST JULLY 2017. Please enclosed GST Registration document.

14. For any clarification OSD may be contacted

15. The Quotationer Should be in PWD/ CPWD Registered. The Registration Document enclosing is must.

प्रति :-

1. सूचना पलट

2. वेब स्थल आई एस आई दिल्ली केन्द्र