

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र



निविदा आमंत्रित सूचना

Tender Notice

निविदा नं. D /ISI /CIVIL WORK /2017 -2018 / 313

ग्राम स्टाटिस्टिका , नई दिल्ली

फ़ोन : 41493984

फैक्स : 41493981

ईमेल : kalam@isid.ac.in

7, एस जे एस , सनसनवाल मार्ग ,
कुतुब होटल के पास
कटवरिया सराय नई दिल्ली

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 02/11/2017 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Subject : - Repairing and Renovation works in C-7 ISI Campus Delhi Centre New Delhi-110016

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).				
	Kiln seasoned and chemically treated hollock wood	cum	0.0231		
2	Providing and fixing flat pressed 3 layer particle board medium density exterior grade (Grade I) or graded wood particle board IS : 3087 marked, to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately):				
	18 mm thick	sqm	6.588		
3	Providing and fixing ISI marked flush door shutters conforming to IS :2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
	35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	sqm	7.141		
4	Providing and fixing 2nd class teak wood lipping/ moulded beading or taj beading of size 18X5 mm fixed with wooden adhesive of approved quality and screws/ nails on the edges of the Pre-laminated particle board as per direction of Engineer-in-charge.	meter	11.64		
5	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete :				
	25 mm dia	meter	13.495		
6	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	each	2		
7	Providing M.S. Piano hinges ISI marked IS : 3818 finished with nickel plating and fixing with necessary screws etc., complete.				
	Overall width 50 mm	meter	7.6		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
8	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :				
	300x16 mm	each	6		
9	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	250x10 mm	each	6		
10	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	125 mm	each	12		
11	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.				
	Twin rubber stopper	each	8		
12	Providing and fixing bright finished 60 mm cup board lock with 2 levers with necessary screws etc complete as per direction of Engineer-in-charge	each	3		
13	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete.				
	Triple strip vertical type	each	4		
14	Providing and fixing to existing door frames.				
	30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames	sqm	2.898		
15	Providing and fixing cup board shutters with 25 mm thick veneered particle board IS : 3097 marked, exterior grade (Grade I), of approved make, including 11nd class teak wood lipping of 25 mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of Engineer-in-Charge.				
	With non decorative veneering on both sides	sqm	3.964		
16	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	sqm	1.08		
17	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size).	cum	1.39684		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
18	12 mm cement plaster finished with a floating coat of neat cement of mix :				
	1:3 (1 cement: 3 fine sand)	sqm	18.624		
19	Providing and fixing glass strips in joints of terrazo/ cement concrete floors.				
	40 mm wide and 4 mm thick	meter	59.8		
20	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	cum	1.39684		
21	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) <u>Single socketed pipes.</u>				
	110 mm diameter	meter	10		
22	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming IS : 5382, leaving 10 mm gap for thermal expansion.				
	Coupler				
	110 mm	each	1		
	Bend 87.5°				
	110 mm bend	each	1		
	Single tee without door				
	110x110x110 mm	each	1		
23	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	One or more coats on old work	sqm	73.074		
24	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In- Charge.	sqm	1.2497		
25	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :				
	Of area 3 sq. metres and below	each	4		
26	Removing & Refixing/dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	2		
27	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	L/S	1 JOB		
28	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls <u>wherever required :</u>				
	Kitchen sink without drain board				
	610x510 mm bowl depth 200 mm	each	1		
29	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
	17.28.2 Flexible pipe				
	32 mm dia	each	1		
30	Providing and fixing 100 mm sand cast Iron grating for gully trap.				
31	Providing and fixing of looking mirror cabinet 390 x 500 x 90 mm pvc (alpina make) with C.P. brass screws and washers complete.	each	1		
32	Providing and fixing towel rod 450 mm long 22 mm diameter CP STAINLESS STEEL	each	1		
33	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:				
	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	each	1		
	Total(inclusive taxes GST)				
	extra taxes(GST) if any				
	Total(inclusive taxes GST)				
	Rebate/discount if any				
	Grand Total (inclusive taxes GST)				

वि.जी. चव्हाण

अभियंता सिविल 'ए'
सूचना

ओएसडी/हेड

- The agency should be done similar nature of work and enclosed the document carrying out the same work.
- प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
- कार्य विवरण CPWD Specification सहित व सिविल अभियंता के शमकश होना चाहिये .
- The Quotationer Should be in PWD/ CPWD Registered. The Registration Document enclosing is must.
- विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "पैन नम्बर " "(जीएसटी)-" नं. लगाना अनिवार्य है .
- The quantity will be increased or decreased as per the actual site condition.
- The agency should carry the work while taking all the safety precaution
- विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
- कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
- माल दुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
- सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
- एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
- काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिम्मेदार नहीं रहेगी.
- The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.
- कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
- (जीएसटी- नं.) GST - No. is a mandatory from of 1ST JULY 2017. Please enclosed GST Registration document.
- For any clarification OSD may be contacted

प्रति :-

- सूचना पलट
- वेब स्थल आई एस आई दिल्ली केन्द्र