


भारतीय सांख्यिकीय संस्थान
दिल्ली केन्द्र



7, एसजेएस, सनसनवाल मार्ग
कुतुब होटल के पास
कटवारिया सराय
नई दिल्ली-110016

ग्राम: स्टैटिस्टिका, नई दिल्ली
फोन: 91.11.41493987
फेक्स: 91.11.41493981
ईमेल : kalam@isid.ac.in

Dtae :- 27/11/16

NOTICE INVITING TENDER

No.D/ISI/CIVIL WORK/2015-16/ 168

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारिख 3/2/16

को 3 .00 P.M. बजे तक इस कार्यालय को मिलने चाहिये. विवरण(quotation) उसी दिन आपके

समक्ष या आपके अनुपस्थिति में 3.30 PM. बजे खोले जायेंगे .

Name of work :- Renovation of main door of D-Block staff quarter.

Sr No.	Description of material size	Unit	Qty	Rate	Amount
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg	399.70		
	rectangular squqre tube				
2	In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	kg	98.893		
3	Providing and fixing ISI marked, IS : 1341, M.S. heavy weight butt hinges with necessary screws etc. complete :Providing and fixing IS : 12817 marked stainless steel butt hinges with stainless steel screws etc. complete :				
	125x90x4.00 mm	each	48		
4	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete :				
	125 mm	each	32		
5	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete				
	300 x 16 mm	each	16		
6	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete :				
	250x10 mm	each	16		
7	Providing and Fixing of Fibre SheetM.S. hasp and staple ncluding pining/starping/nut-bolting etc.with approved make as per the engineer-in-charge including cutting, hoisting, fixing in position	sqm	12.125		

Sr No.	Description of material size	Unit	Qty	Rate	Amount
8	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete.	sqm	10.24		
	With 12 mm mild steel U beading				
9	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : whole side including.	meter	160.18		
	total inclusive taxes			Total	

Schannan

4
दस्तावेज 31/11/16
ओएसडी 27/11/16

अभियंता सिविल 'अ'

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए
3. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
4. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
5. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
6. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
7. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
8. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
9. सिविल कार्य नए सि पि डब्लू डी विवरण(specification) सहित व सिविल अभियंता के समक्ष होना चाहिये .
10. अगर कोटेशन में कुछ चीजे छुटती है तो सीधे सीधे आपको DSR अथवा मार्किट बेस से जो भी कम है वह दिया जाएगा.
11. कांटेक्टर द्वारा लगाये गए आयरन वर्क (स्टील वर्क) कांटेक्टर और इंजीनियर सिविल के शमक्ष (weight) वजन किया जायेगा. वही एकचुअल (weight) वजन माना जायेगा.
12. अगर (वर्क) काम में कुछ भी अनियमितता दिखाई देती है तो उसे तुरंत स्पष्टता के साथ करे. अन्यथा पेमेंट (PAYMENT) नहीं दिया जायेगा. कोटेशन के अनुसार ही पेमेंट दी जाएगी.