

INDIAN STATISTICAL INSTITUTE

DELHI CENTRE

Gram: STATISTICA, NEW DELHI

7, SJS, SANSANWAL MARG

Phone: 91-11-41493980

Fax: 91-11-41493981

Email: kalam@isid.ac.in



NEAR QUTUB HOTEL
KATWARIA SARAI
NEW DELHI-110016.

ISID/EMU/PPRU/2017-18/ 26

Date: 08-11-2017

निविदा दर सूची Tender Quotation

कार्य का नाम : पीपीआरयू केबल तथा डीबी फिक्सिंग, मीटर कार्य को कार्यालय परिसर में ही किया जाना है। कृपया उस परिक्षेत्र का निरीक्षण कर लें जहां पर कार्य किया जाना है तथा अपनी मोहरबंद निविदाएं (Sealed Quotations) हमारे पास 22/11/2017 को 3 बजे तक या उससे पहले भेज दें। निविदाएं विशेष कार्य अधिकारी भारतीय सांख्यिकीय संस्थान दिल्ली द्वारा 3 बजे तक प्राप्त की जाएंगी तथा उसी दिन 3.30 बजे खोली जाएंगी। जिन मदों के लिए दरें उद्धृत की जानी हैं वे संलग्न विवरणी में हैं। संस्थान को यह अधिकार है कि वह बिना कोई कारण बताए एक या सभी निविदाओं को अस्वीकृत कर दे या कार्य के हिस्सों को अलग अलग एजेंसियों को आवंटित कर दे


Name of the work: PPRU cable and DB fixing, meters works are to be carried out in our Institute premises. Kindly inspect the premises where the work has to be carried out and send your **sealed quotations** to reach us **on or before 22.11.2017**. Tender will be received up to **03.00 pm** by The **Officer on Special Duty**, Indian Statistical Institute Delhi centre and will be opened on the same day at **03.30 PM**. The items for which rates are to be quoted are given in the enclosed statement. The Institute reserves the right to reject any or all the quotations or to allot parts of the work to different agencies without assigning any reason.

S.no	Description of items	Qty	Unit	Rate in Rs.	Amount
1	Cabling Work.				
	Supply, Installation and testing, commissioning of 1100V, XLPE insulated and sheathed following Aluminum, armoured, UG cable with necessary earthing work. Make: (Havells, Polycab, Finolex)				
1.1	Cable laying in the soil with bricks on both side and top with sand cushion etc and completion of work as directed by engineering in charge.				
1..1.1	4 x 25 Sq mm Aluminum conductor (PVC).	60	mts		
1.2	End termination of the following 1100V grade XLPE				

	insulated AR/ Aluminum conductor UG cables including supply of single compression cable gland crimping lugs and gland earthing.				
1.2.1	4 X 25 sq mm Aluminum conductor (PVC)	2	nos		
2	MCB Distribution boards				
	The removing of existing Dbs and Supply, installation ,testing and commissioning of following three phase vertical TPN, MCB DB,415 volts, on surface/, recess, complete with loose wire box, terminal connectors for all incoming and outgoing circuits, duly prewired with suitable size FRLS PVC insulated copper conductor up to terminal blocks, tinned copper bus bar, neutral bus bar earth bar, din bar, detachable gland plate, interconnections, powder painted including necessary earthing etc. as required (But without MCB,MCCB,RCCB)DB should be fix in concealed in wall, including civil works. (Havells, Legrand, Hager)				
2.1	4+18 way, double door	2	nos		
3	S/F C series, RCCB				
	Supply and fixing following rating, four pole,(three phase and neutral),415 volts, residual current circuit breaker (RCCB),having a sensitivity current upto 300 mA in the existing MCB DB complete with connection testing and commissioning ect. As required.				
3.1	63 Amps (Havells, Legrand,Hager)	2	nos		
4	S/F C series, SP MCB				
	Supply and fixing following rating, 5 Amps to 32 amps rating, 240 volts 'C' curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning ect. As required.				
4.1	5-32 amps Single pole (Havells, Legrand,Hager)	36	nos		



5	Three phase four wire, whole current ampere meter ,direct reading type, LEDs indicating presence of each phase Withstands 440V between phase and neutral Maintains accuracy under current reversal conditions High surge withstand capability up to 8kV. Frequency 50 Hz \pm 5 %				
5.1	current ratings 20-100 A	2	nos		
6	Supply and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
6.1	25 mm	30	mtrs		
				Total Rs.	


 08/11/2017
 Officer on -Special- Duty

नियम एवं शर्तें

Terms and Conditions

- कार्य को के०लो०नि०वि० मानकों के अनुसार किया जाना है ।
The work shall be carried out as CPWD norms.
- अभियांत्रिकी प्रभारी की देख रेख के तहत कार्य को पूरा किया जाएगा ।
The work shall be carried out under the supervision of the Engineering In- Charge.
- कार्य में उपयोग करने से पहले सामग्री को अनुमोदित करवाया जाएगा ।
The material shall be got approved before use on work.
- कार्य की समाप्ति के उपरान्त बेकार सामान हटा देना है ।
The waste should be removed after completion of work.
- निविदाकार को जीटिन तथा पिन संख्या अवश्य उद्धृत करनी है जिसके बिना दरों पर विचार नहीं किया जाएगा ।
Contractor shall be furnished the ⁵GTIN and PIN, without which Quotation will be not be considered.
- अहस्ताक्षरित दर सूची पर विचार नहीं किया जाएगा ।
Without signature quotation will not be considered

प्रतिलिपि:

भारतीय सांख्यिकी संस्थान वैबसाईट/नोटिस बोर्ड

Copy to : ISI Website/Notice Board.

