


भारतीय सांख्यिकीय संस्थान
दिल्ली केन्द्र

ग्राम: स्टाटिस्टिका, नई दिल्ली
फोन: 91.11.41493987
फेक्स: 91.11.41493981
ईमेल : kalam@isid.ac.in



7, एसजेएस, सनसनवाल मार्ग
कुतुब होटल के पास
कटवारिया सराय
नई दिल्ली-110016

Dtae : -09/12/2015

NOTICE INVITING TENDER

No.D/ISI/CIVIL WORK/2015-16/ 161

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 15/12/2015 को 3 .00 P.M. बजे तक इस कार्यालय को मिलने चाहिये. विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 PM. बजे खोले जायेंगे .

Name of work :- Providing and Laying of Flooring and Wall Tiles in Doctor Room, at I.S.I., Delhi Centre

Sr No.	Description of material size	Unit	Qty	Rate	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead.				
	for thickness of tile above 25 mm and up to 40mm	sqm	24.25		
	VITRIFIED FLOOR TILES				
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.				
	Size of Tile 600x600 mm	sqm	24.25		
3	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	33.885		
4	Removing and Refixing of wash basin china type pedestal	1 job	1		
5	Malawa removed out side the campus	1 job	1		
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	One or more coats on old work	sqm	7.8752		
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.				

	Cement mortar 1:3 (1 cement :3 coarse sand)	sqm	1.84		
8.	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	sqm	3.68		
9	Finishing walls with Acrylic Smooth exterior paint of required shade :				
	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	1.84		
10	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty:				
	Float glass panes of thickness 5.5 mm	sqm	2.88		
11	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	21.75		
12	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :				
	Old work (one or more coats)	sqm	21.25		
	inclusive taxes			Total	

Schano

अभियंता सिविल 'अ'

Koushik
09/12/2015
ओएसडी

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य आदेश मिलने के बाद 10 दिन के भीतर कार्य समाप्त होना चाहिए
3. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
4. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
5. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
6. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
7. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
8. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
9. सिविल कार्य नए सि पि डब्लू डी विवरण(specification) सहित व सिविल अभियंता के समक्ष होना चाहिये