


भारतीय सांख्यिकीय संस्थान
दिल्ली केन्द्र

ग्राम: स्टाटिस्टिका, नई दिल्ली
फोन: 91.11.41493987
फेक्स: 91.11.41493981
ईमेल : kalam@isid.ac.in



7, एसजेएस, सनसनवाल मार्ग
कुतुब होटल के पास
कटवारिया सराय
नई दिल्ली-110016

Date : -09/12/2015

NOTICE INVITING TENDER
No.D/ISI/CIVIL WORK/2015-16/ 162

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 16/12/2015 को 3 .00 P.M. बजे तक इस कार्यालय को मिलने चाहिये. विवरण(quotation) उसी दिन आपके समक्ष या आपके अल्पस्थिति में 3.30 PM. बजे खोले जायेंगे .

Name of work :- Providing and Laying of Flooring Tiles in GH Room no 16, Guest House Lounge Room at I.S.I., Delhi Centre

Sr No.	Description of material size	Unit	Qty	Rate	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead. for thickness of tile above 25 mm and up to 40mm	sqm	63.01		
2	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make in colours such as White, lovery,Grey,Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc., complete	sqm	20.70		
3	Deduct for not using 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles.	sqm	20.70		
4	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.	sqm	20.75		
VITRIFIED FLOOR TILES					
5	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	sqm	42.30		
6	Deduct for not using 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles. Size of Tile 600x600 mm	sqm	42.30		

Sr No.	Description of material size	Unit	Qty	Rate	Amount
7	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.	sqm	42.30		
8	Malawa removed out side the campus	1 job	1		
	inclusive taxes			Total	

Scharam

अभियंता सिविल 'अ'

4
असह 311/2/15
09/12/2015
ओएसडी

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य आदेश मिलने के बाद 10 दिन के भीतर कार्य समाप्त होना चाहिए
3. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
4. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
5. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
6. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
7. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
8. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
9. सिविल कार्य नए सि पि डब्लू डी विवरण(specification) सहित व सिविल अभियंता के समक्ष होना चाहिये .