

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र



निविदा आमंत्रित सूचना

Tender Notice

निविदा नं. D/ISI/CIVIL WORK/2017-2018/१४४

ग्राम स्टैटिस्टिका, नई दिल्ली
फ़ोन : 41493984
फैक्स : 41493981
ईमेल : kalam@isid.ac.in

7, एस जे एस, सनसनवाल मार्ग,
कुतुब होटल के पास
कटवरिया सराय नई दिल्ली

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं। विवरण(quotation) तारीख 03/07/2017 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये। विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे।

Name of work : Painting and other civil works in B-1 ISI Campus Delhi Centre, New Delhi-110016

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	303.85		
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade: Old work (one or more coats)	sqm	287.74		
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. for item no. 1 of 40%	sqm	115.09		
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	sqm	169.95		
5	Providing and fixing nickel plated M.S. pipe curtain rods with nickel plated brackets : 25 mm dia. (heavy type)	meter	9.6		
6	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhat, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	each	9		
7	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	4.79		
8	sanitary installation work C.P.V.C. PIPES (astral make) Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This excludes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 20 mm nominal outer dia Pipes				
9	3/4" - Providing and Fixing CPVC plain Tee (Astral)	each	15		
10	3/4" - Providing and Fixing CPVC plain elbow (Astral)	each	31		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
11	3/4"-1/2" - Providing and Fixing CPVC brass elbow (Astral)	each	21		
12	3/4"-1/2" - Providing and Fixing CPVC brass Tee (Astral)	each	21		
13	1/2"-3/4" CPVC Male Adapter brass threaded.	each	11		
14	3/4"-1/2" - Providing and Fixing CPVC female adaptor brass (Astral)	each	4		
15	Providing and fixing uplasticised PVC connection pipe with brass unions :: 45 cm length 15 mm nominal bore	each	10		
16	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore	each	14		
17	Providing and fixing C.P. brass 2 in 1 bib cock for basin mixer and geyser points of approved quality conforming to IS:	each	2		
18	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	each	6		
19	over head shower 85 mm dia with single flow and shower arm	each	2		
20	Providing and fixing C.P. brass filler cock of approved quality conforming to IS:8931 : 15 mm nominal bore	each	4		
21	providing and fixing of upvc pipe (1.5")	meter	4		
22	providing and fixing elbow plain (1.5")	each	8		
23	HEALTH FOUKET WITH CP TUBE	each	2		
24	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm dia	each	3		
25	cp waste coupling-1.25"	each	2		
26	providing and fixing cp brass consealed 1/2"	each	4		
27	Providing and fixing white vitreous china pedestal type wafer closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid	each	1		
28	Providing and fixing controlled flush, low level cistern made of vitreous china with all fittings complete. 10 litre (full flush) capacity-white	each	1		
29	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	each	2		
30	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete.	each	2		
30-a	Providing and fixing stainless steel towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 450 mm long towel rail with total length	each	2		

Sr.No.	Description of item of work.	Unit	Qty	Rate	Amount
31	Providing and fixing Stainless Steel/A ISI 304 (0.500 x 1.080 depth 0.200 mm) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :				
	Kitchen sink without drain board	each	1		
32	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour and shade; with necessary screws etc. complete,				
	Twin rubber stopper	each	6		
33	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia, 0.50 mm all complete..				
	With 2nd class teak wood beading 62X19 mm	sqm	2.1		
34	Removing and refixing of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	4		
35	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) :				
	With F.P.S.(non modular) bricks	cum	0.117		
	CERAMIC GLAZED TILES				
35	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	30.744		
36	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red, Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc., complete..	sqm	0		
37	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	43.92		
38	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by echanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	15 mm to 40 mm nominal bore	meter	31.625		
39	malaba removing outside the campus	1 job	1		
40	Providing and fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete.				
	40 mm	each	7		
41	Providing and fixing 50 mm bright finished brass cupboard or wardrobe knob of approved quality with necessary screws.	each	14		
42	Providing and fixing 2nd class teak wood lipping/ moulded beading or taj beading of size 18X5 mm fixed with wooden adhesive of approved quality and screws/ nails on the edges of the Pre-laminated particle board as per direction of Engineer-in-charge	meter	5.3		

Sr.No.	Description of item of work	Unit	Qty	Rate	Amount
43	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete. Triple strip vertical type	each	14		
44	Extra for providing ISI marked Stainless Steel butt hinges instead of M.S. pressed butt hinges bright finished of required size with necessary screws. (Shutter area to be measured).	sqm	0.7743		
45	Providing and fixing 25 mm thick shutters for cup board etc. : Panelled or panelled & glazed shutters ; Second class teak wood including ISI marked anodised aluminium butt hinges with necessary screws	sqm	0.7743		
46	Providing and fixing plywood 12 mm thick, for use self in cupboard with necessary screws, including priming coat on unexposed surface with	sqm	1.7976		
47	Providing and fixing rain water upvc pipes (prince/astrol/ Total (inclusive as per applicable taxes)	meter	10		

श्री. जी. जहाज

अभियंता सिविल 'अ'
सूचना

21/6/2017
ओएसडी

- प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
- कार्य विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
- कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
- विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी लट" "पल नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
- The quantity will be increased or decreased as per the actual site condition.
- विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
- कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
- माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
- सिक्योरिटी डिपोजिट 4% सुरक्षित जमा राशि आपके कुल राशि पर 6 महीने के लिए वैध रहेगी.
- एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेगी .
- काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिम्मेदार नहीं रहेगी.
- The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any
- Before chemical laying it show to the Engineer Civil

पति :-

- सूचना पलट
- वेब स्थल आई एस आई दिल्ली केंद्र