## भारतीय सांख्यिकी संस्थान दिल्ली केंद्र

ग्राम स्टास्टिस्टिका , नई दिल्ली फोन : .41493984 फैक्स : 41493981 ईमेल : <u>kalam@isid.ac.in</u>



7 , एस जे एस , सनसनवाल मार्ग , कुतुब होटल के पास कटवरिया सराय नई दिल्ली

## निविदा आमंत्रित सूचना

**Tender Notice** 

निविदा जं. D /ISI /CIVIL WORK /2017 -2018 / २९७७

मोहरबद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं .विवरण(quotation) तारिख 30/06/2017 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3,30 बजे खोले जायेंगे

Name of work - Painting and other civil works in B-LI ISI Campus Delhi Centre, New Delhi-110016

Sr No.	Description of item of work	Unit	1		T
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	Qty 303.85	Rate	Amount
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade				
	Old work (one or more coats)	sqm	287,74		
3	Providing and applying white coment based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.				
	for Item no Lof 40%	sqm	115.1		
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :		14.5.1		
	Dne or more coats on old work	sqm	169.95		
	Providing and fixing nickel plated MIS, pipe curtain rods with nickel plated brackets (				
	25 mm dia (heavy type)	meter	9.6		
	Distribunding/demolishing	menor	- 3.0		_
	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead (				
	Of area 3 sq. metres and below	each	9		_
7	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including outting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In- Sharge.		2		
	With cement mortar 1:4 (1 cement 4 fine sand)				
С В В	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste naterials by merihanical means, including loading, transporting. loading to pproved municipal dumping ground or as approved by Engineer-in-charge. reyond 50 m initial lead, for all leads including all lifts wolved.	sqm 1 job	1		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
9	Providing and fixing ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all collours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and datos, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per som, including pointing in white cement mixed with pigment of matching shade complete.	sqm	5,037		
10	Finishing walls with Acrylic Smooth exterior paint of required shade:				
	Old work (Two or more cost applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	sqm	13		
	inclusive taxes			Total	

- तिहुजी, खब्हा वि

अभिवंता सिंबिल 'अ' संचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवाय है .

2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमक्श होना चाहिये .

3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.

4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .

5. The quantity will be increased or decreased as per the actual site condition.

6. विवरण फामें(quotation) सिम्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे बिरस्त किया जाएगा .

7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.

8. माल ढूलाई का अतिरिक्त किराया भाडा या कुरियर भाडा नहीं दिया जायेगा.

सिक्योरिटी डिपाजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.

10. एडवांस राशि काम के पहले या बाद में एपलीकेबल नहीं रहेंगे .

11 काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिसेदार नहीं रहेगी.

12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.

प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र

Aler Aler