

Date:- 07/10/2014

भारतीय सांख्यिकीय संस्थान
दिल्ली केन्द्र

ग्राम: स्टाटिस्टिका, नई दिल्ली
फोन: 91.11.41493987
फेक्स: 91.11.41493981
ईमेल : kalam@isid.ac.in



7, एसजेएस, सनसनवाल मार्ग
कुतुब होटल के पास
कटवारिया सराय
नई दिल्ली-110016

NOTICE INVITING TENDER

Tender No. D/ISI/CIVIL WORK/2015-16/ 136

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 19/10/2014 को 3.00 बजे तक इस कार्यालय को मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

NAME OF WORK :-Painting Works in B-5 Flats ISI campus , Delhi centre, New Delhi.

Sr no.	Description of item of work	Unit	Qty	Rate	Amount
1	Removing dry or oil bound distemper, water proffing cement paint and the like by scrapping, sand preparing and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	229.18		
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)	sqm	229.18		
3	White washing with lime to give an even shade : Old work (two or more coats)	sqm	41.174		
4	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	41.174		
5	Providing and applying white cement based putty of average thickness 1 mm , of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete				
	40 % paid of total quantity of item no. 1	sqm	91.67		
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :				
	With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	3.15		
7	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, loading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1 job	1		

Sr no.	Description of item of work	Unit	Qty	Rate	Amount
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shad: (Two or more coats on new work)	sqm	27.744		
				Total	

Schamam

अभियंता सिविल 'अ'

11/11/15
कॉन्सट्रक्शन
ओएसडी 08/10/2015

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. सिविल कार्य नए सि पि डब्लू डी विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 20 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टेन नम्बर " लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
- 11.कार्य करते समय किसी भी प्रकार का हादसे के लिए ISI जिमेदार नहीं रहेगी.

प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र