

Date :- 22/02/2017

Indian Statistical Institute  
Delhi Centre

Note

Subject: - Water pipelines work for cleaning of solar panel in terrace of teaching block, faculty block, and old hostels block in ISI Campus Delhi Centre New Delhi-110016

Ref: - NO.D/ISI/Civil Work/2016-17/264 Dated 21/02/2017

With reference to the above subject work only two quotations have been received at the stipulated date(21/02/2017) and time, of 1) M/s Pintu Construction Co. 2) M/s. Amit Trading Co. Since the sufficient no. of quotations have not been received in stipulated date and time. It is proposed to again extend the Tender to 28/02/2017 (upto 3.00 pm). Submitted for approval please.



Engineer Civil A 22/2/2017.

Recommended for extension of date to 28/2/2017


OSD

Karan Arora  
22/2/2017

agbhatt  
Head 22/2/2017

ISI, Delhi Centre

भारतीय सांख्यिकी संस्थान  
दिल्ली केंद्र



ग्राम स्टाटिस्टिका , नई दिल्ली  
फ़ोन : .41493984  
फैक्स : 41493981  
ईमेल : [kalam@isid.ac.in](mailto:kalam@isid.ac.in)

7 , एस जे एस , सनसनवाल मार्ग ,  
कुतुब होटल के पास  
कटवरिया सराय  
नई दिल्ली

निविदा आमंत्रित सूचना

निविदा नं. D /ISI /CIVIL WORK /2016 -2017 / 264

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 21/02/2017 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

water pipelines work for cleaning of solar power panel in terrace of teaching block, faculty block and old hostel block in ISI Campus Delhi Centre New Delhi-110016.

SR.No.	DESCRIPTION OF WORK	unit	Qty.	Rate	Amount
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, excluding all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.C.P.V.C. PIPES{astral make}				
	20 mm nominal outer dia Pipes	meter	130		
2	Providing and fixing ball valve of approved quality, High or low pressure, with plastic floats complete : ( PRAYAG)	each	2		
	20 mm nominal bore				
3	Providing and fixing CPVC (ASTRAL/ASHIRWARD/PRINCE) BALL VALVE(GATE VALVE) approved quality				
	20 mm nominal bore	each	3		
4	Providing and fixing CPVC Union ( Astral)-3/4"	each	3		
5	3/4"-1/2" - Providing and Fixing CPVC MALE ADAPTOR-BRASS	each	1		
6	3/4"Providing and Fixing CPVC FEMALE ADAPTOR-BRASS	each	3		
7	Providing and Fixing GI-TEE-1/2"	each	1		
8	Providing and Fixing GI-ELBOW-1/2"	each	2		
9	Providing and Fixing GI-UNION-1/2"	each	1		
10	Providing and Fixing cpvc tank connection-3/4"-3/4"	each	3		
11	Providing and Fixing GI NIPPLE--1/2"-L-3"	each	3		
12	3/4"-3/4" - Providing and Fixing CPVC TEE-Plain	each	3		
13	3/4"-3/4" - Providing and Fixing CPVC FT-Plain	each	2		
14	3/4"-3/4" - Providing and Fixing CPVC ELBOW-Plain	each	8		
15	3/4"-1/2" - Providing and Fixing CPVC ELBOW-BRASS	each	5		
16	3/4"- Providing and Fixing CPVC COUPLER(SOCKET)	each	40		
17	3/4"-1/2" - Providing and Fixing CPVC TEE-BRASS	each	3		
18	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.				

SR.N <sup>o</sup>	DESCRIPTION OF WORK	unit	Qty.	Rate	Amount
	15 mm nominal bore	each	9		
19	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.				
	Circular tank( syntex make)	per/litre	2000		
	<b>Civil Work</b>				
	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.				
	<b>ISMB(100 X 75 )</b>	kg	110.4		
	<b>ISNT 50 -50 X 50 -6 MM THICK -4.5KG/MTR</b>	kg	82.8		
21	Providing sand stone slab for roofing and laying them in cement mortar 1 : 4 (1 cement : 4 coarse sand) over wooden karries or R.C.C. battens or structural steel sections (Karries or battens or structural steel sections to be paid separately), including pointing the ceiling joints with cement mortar 1:3 (1 cement : 3 fine sand ) complete :				
	12.23.1 Red sand stone slab				
	40 to 50 mm thick	sqm	8.96		
22	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) :				
	With F.P.S.(non modular) bricks	cum	0.3809		
23	12 mm cement plaster :				
	1:4 (1 cement : 4 coarse sand)	sqm	6.624		
	<b>REINFORCED CEMENT CONCRETE</b>				
24	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	cum	0.4		
	<b>Total (inclusive taxes)</b>		<b>Total</b>		

*Beharam*

अभियंता सिविल 'अ'

1 अक्षर 31/02/17  
ओएसडी 08/2/2017

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .

SR.No	DESCRIPTION OF WORK	unit	Qty.	Rate	Amount
-------	---------------------	------	------	------	--------

2. का. विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या कूरियर भाड़ा नहीं दिया जायेगा.
9. सिक््योरिटी डिपाजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.
13. Malaba removing outside the campus at own cost.

प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र