भारतीय सांख्यिकी संस्थान दिल्ली केंद्र

ग्राम स्टास्टिस्टिका , नई दिल्ली फ़ोन : .41493984 फैक्स : 41493981 ईमेल : <u>kalam@isid.ac.in</u>



7, एस जे एस , सनसनवाल मार्ग , कुतुब होटल के पास कटवरिया सराय नई दिल्ली

निविदा आमंत्रित सूचना

निविदा नं. D /ISI /CIVIL WORK /2016 -2017 / 24 9

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते है . विवरण(quotation) तारिख 09/12/2016 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

NAME OF WORK :-Painting and other Civil Work in Admin Block/conference Room/Seminar Room ISI Campus Delhi Centre New Delhi.

SR.No.	DESCRIPTION OF WORK	unit	Qty	Rate	Amount
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	73.73		
2	Distempering with oil bound washable distemper of approved brand and anufacture to give an even shade :	sqm	87.47		
	Old work (one or more coats)		1		
3	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	28.33		
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer- In-Charge.				
	With cement mortar 1:4 (1cement: 4 coarse sand)	sqm	28.33		
5	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	28.33		
6	Finishing walls with Acrylic Smooth exterior paint of required shade:	sqm	45.2		
	Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface				
7	Polishing on wood work with ready made wax polish of approved brand and manufacture :				
	Old work	sqm	24.06		
8	Painting G.I. pipes and fittings with synthetic enamel white paint with two coats over a ready mixed priming coat, both of approved quality for new work :				
	50 mm diameter pipe	meter	57.44		

ŠR.No.	DESCRIPTION OF WORK	unit	Qty	Rate	Amount
9	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	sqm	5.6	T	
	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush				
	12.5 mm thick tapered edge gypsum moisture resistant board	sqm	5.6		
12	Providing and fixing plywood 4 mm thick, one side decorative veneer conforming to IS: 1328 (type-1), for plain lining / cladding with necessary screws, including priming coat on unexposed surface with :	sqm	1		
13	Decorative veneer facings of approved manufacture door repairing work such as removing refixing of door with repairing of hinges, cutting and grinding etc. welding work whenever required	l/s	6		
	total (inclusive taxes)			Total	

Schavar

अभियंता सिविल 'अ'

भ जा मा मा मा जन्मा मा मा मा मा ओएसडी

SR.No.	DESCRIPTION OF WORK	unit	Qty	Rate	Amount
ł					

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .

2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमक्श होना चाहिये .

3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.

4. विवरणकर्त्ता(quotationer) विवरण फार्म(quotation) के साथ ''डी वट'' ''पन नम्बर '' ''टिन नम्बर '' लगाना अनिवार्य है .

5. The quantity will be increased or decreased as per the actual site condition.

6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .

7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.

8. माल ढूलाई का अतिरिक्त किराया भाड़ा या क्रियर भाड़ा नहीं दिया जायेगा.

9. सिक्योरिटी डिपाजिट ५% स्रक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.

10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .

11.काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.

12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at 13. After completion of work the entire room may be cleaned by contractor at his own cost. प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र