

भारतीय सांख्यिकी संस्थान

दिल्ली केंद्र

ग्राम स्टाटिस्टिका , नई दिल्ली

फ़ोन : .41493984

फैक्स : 41493981

ईमेल : [kalam@isid.ac.in](mailto:kalam@isid.ac.in)



7 , एस जे एस , सनसनवाल मार्ग ,  
कुतुब होटल के पास  
कटवरिया सराय नई दिल्ली

निविदा आमंत्रित सूचना

Tender Notice

निविदा नं. D /ISI /CIVIL WORK /2017 -2018 / 330

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 07/02/2018 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Subject : - Providing and Fixing of ALUMINIMUM PARTITION for separate chamber and flooring tile work in ACCOUNT SECTION in ISI Campus Delhi Centre New Delhi-110016					
Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Hacking of CC flooring including cleaning for surface etc.complete as per direction of the Engineer-in-Charge.	sqm	45.97		
2	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).				
	Size of Tile 600x600 mm	sqm	45.97		
3	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in-charge.				
	Size of Tile 600x600 mm	sqm	45.97		
4	Deduct for not grouting the joints with white cement and matching pigment in the items of fixing of vitrified tiles.	sqm	-45.97		
5	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	sqm	23.24		
	ALUMINIUM WORK				

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
6	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	For fixed portion				
	Powder coated aluminium (minimum thickness of powder coating 50 micron)	kg	86.98		
	partitiuon section				
	sl no. 18-section no. 20005-63.50 x 38.10 thickness t=3.18 mm kg= 1.777kg/mtr				
	glazing-sl no. 719377-A-1.20 kg= 0.154 kg/mtr				
7	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge.				
	Pre-laminated particle board with decorative lamination on both sides	sqm	61.254		



Sr No.	Description of item of work	Unit	Qty	Rate	Amount
--------	-----------------------------	------	-----	------	--------

5. The quantity will be increased or decreased as per the actual site condition.

6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .

7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.

8. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.

9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.

10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .

11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.

**12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.**

**13. (जीएसटी- नं.) GST - No. is a mandatary from of 1ST JULLY 2017. Please enclosed GST Registration document.**

14. For any clarification OSD may be contacted

**15. The Quotationer Should be in PWD/ CPWD Registered. The Registration Document enclosing is must.**

**16. some items may or may not be operated at the time situational cnondition.**

प्रति :-

1. सूचना पलट

2. वेब स्थल आई एस आई दिल्ली केन्द्र

य  
ओ.एस.डी. आ.नं.  
01/2/2018