

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र

ग्राम स्टैटिस्टिका , नई दिल्ली

फ़ोन : .41493984

फैक्स : 41493981

ईमेल : kalam@isid.ac.in



7 , एस जे एस , सनसनवाल मार्ग ,
कुतुब होटल के पास
कटवरिया सराय
नई दिल्ली

निविदा आमंत्रित सूचना

निविदा नं. D /ISI /CIVIL WORK /2016 -2017 /

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 09/08/2016 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Name of Work : - Toilet Renovation work inB-4 in ISI Campus Delhi Centre, New Delhi-110016.

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc, complete.	sqm	12.4		
2	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc, complete	sqm	47.322		
3	White washing with lime to give an even shade : Old work (two or more coats)	sqm	47.322		
4	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below	each	2		
5	Taking out flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	4		
6	Refixing of flushing cistern of all types (C.I./PVC/Vitrious China)	each	4		
7	malaba removing outside campus	1job	1		
8	Making nani trap with				
a	3"-UPVC ELBOW-90 deg. Elbow-soc	each	1		
b	3"-upvc pipe-	meter	2.5		
c	excavation work	l/s	1		
d	concreting work	l/s	1		
9	Providing and Fixing of CP Floor JALI of 100 mm dia	each	2		
10	Providing and fixing to existing door frames.				
	30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames.(sample is kept in D-13)	sqm	2		
	STAINLESS STEEL FITTING				
11	Providing and fixing IS : 12817 marked stainless steel butt hinges (heavy weight) with stainless steel screws etc. complete :				

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
	125x64x2.50 mm	each	6		
	ANODISED ALUMINIUM FITTINGS (ALL FITTINGS SHALL BE ISI MARKED)				
12	Providing and fixing aluminium sliding door bolts, ISI marked anodised anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :				
	250x16 mm	each	4		
13	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	250x10 mm	each	4		
14	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
	125 mm	each	4		
	Total (inclusive taxes)			Total	

Bhanu

अभियंता सिविल 'अ'

agbhatt
ओएसडी : 1/1/23

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमक्ष होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर" "टिन नम्बर" लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition. The payment will be made in an actual basis.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.
13. कांटेक्टर द्वारा लगाये गए आयरन वर्क (स्टील वर्क) कांटेक्टर और इंजीनियर सिविल के शमक्ष (weight) वजन किया जायेगा. वही एकचुअल (weight) वजन माना जायेगा.
14. अगर (वर्क) काम में कुछ भी अनियमितता दिखाई देती है तो उसे तुरंत स्पष्टता के साथ करे. अन्यथा पेमेंट (PAYMENT) नहीं