

तारीख: - 27/02/2018

भारतीय सांख्यिकी संस्थान  
दिल्ली केंद्र

ग्राम स्टाटिस्टिक्स, नई दिल्ली

फ़ोन : 41493984

फैक्स : 41493981

ईमेल : [kalam@isid.ac.in](mailto:kalam@isid.ac.in)



7, एस जे एस, सनसनवाल मार्ग,  
कुतुब होटल के पास  
कटवरिया सराय नई दिल्ली

निविदा आमंत्रित सूचना

Tender Notice


निविदा नं. D /ISI /CIVIL WORK /2017 -2018 / 340

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 16/03/2018 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .


Name of work - Renovation of Flooring Tile/Concreting Work in Incharge of Electrical Engineer in ISI Campus Delhi Centre New Delhi-110016

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	sqm	18.72		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size).	cum	3.74		
3	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete.	sqm	18.72		
	Size of Tile 600x600 mm				
4	Taking out existing wooden/steel/partition/aluminum door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.and then refixing as per complete				
	STEEL REINFORCEMENT				
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
	Thermo-Mechanically Treated bars of grade Fe-500 D or more.	kg	51.745		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
	8 mm dia= 0.395kg/mtr				
	Total(inclusive taxes)				
	extra taxes if any				
	Total(inclusive taxes)				
	Rebate/discount if any				
	Grand Total (inclusive taxes)				



अभियंता सिविल 'ए'

  
ओएसडी  
27/2/2018

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "पैन नम्बर " "(जीएसटी)-" नं. लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.
13. (जीएसटी- नं.) GST - No. is a mandatory from of 1ST JULY 2017. Please enclosed GST Registration document.
14. For any clarification OSD may be contacted
15. The Quotationer Should be in PWD/ CPWD Registered. The Registration Document enclosing is must.

प्रति :-

1. सूचना पलट
2. वेब स्थल आई एस आई दिल्ली केन्द्र