

भारतीय सांख्यिकी संस्थान  
दिल्ली केंद्र

ग्राम स्टैटिस्टिका , नई दिल्ली  
फ़ोन : .41493984  
फैक्स : 41493981  
ईमेल : [kalam@isid.ac.in](mailto:kalam@isid.ac.in)



7, एस जे एस, सनसनवाल मार्ग,  
कुतुब होटल के पास  
कटवरिया सराय  
नई दिल्ली

निविदा आमंत्रित सूचना

निविदा नं. D /ISI /CIVIL WORK /2016 -2017 / 240


मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 28/11/2016 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Name of work - Painting and Other Civil Works in A-11, in ISI Campus Delhi Centre, New Delhi-110016

| Sr No. | Description of item of work   | Unit | Qty    | Rate | Amount |
|--------|---|------|--------|------|--------|
| 1      | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.  | sqm  | 378.06 |      |        |
| 2      | Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :  |      |        |      |        |
|        | Old work (one or more coats)  | sqm  | 378.06 |      |        |
| 3      | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :   |      |        |      |        |
|        | One or more coats on old work   | sqm  | 151.86 |      |        |
| 4      | Providing and fixing nickel plated M.S. pipe curtain rods with nickel plated brackets :   |      |        |      |        |
|        | 25 mm dia (heavy type)  | sqm  | 14.09  |      |        |
| 5      | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :   |      |        |      |        |
|        | Of area 3 sq. metres and below  | sqm  | 13.836 |      |        |
|        | Of area beyond 3 sq. metres   | sqm  | 7.68   |      |        |
| 6      | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.  |      |        |      |        |
|        | Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)  | cum  | 0.063  |      |        |
| 7      | Providing and fixing Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately). |      |        |      |        |
|        | 18 mm thick   | sqm  | 1.8    |      |        |
| 8      | Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.  | each | 2      |      |        |



| Sr No. | Description of item of work   | Unit | Qty    | Rate  | Amount |
|--------|---|------|--------|-------|--------|
| 9      | Removing the existing washbasin and refixing the new place (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.  | each | 2      |       |        |
| 10     | Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.   |      |        |       |        |
|        | 5 mm thick  |      |        |       |        |
|        | 1 mter = 2.95kg   | kg   | 54.87  |       |        |
| 11     | Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) : 6.3.1 With F.P.  |      |        |       |        |
|        | With F.P.S.(non modular) bricks   | cum  | 0.1127 |       |        |
| 12     | CEMENT PLASTER (IN COARSE SAND)   |      |        |       |        |
|        | 12 mm cement plaster of mix :   |      |        |       |        |
|        | 1:4 (1 cement: 4 coarse sand)   | sqm  | 0.49   |       |        |
| 13     | 15 mm cement plaster on rough side of single or half brick wall of mix:   |      |        |       |        |
|        | 1:4 (1 cement: 4 coarse sand)   | sqm  | 0.49   |       |        |
| 14     | Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.   |      |        |       |        |
|        | for item no. 2 of 40%   | sqm  | 151.22 |       |        |
| 15     | Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. | sqm  | 4.58   |       |        |
| 16     | malaba removing outside the campus  | l/s  | 1      |       |        |
|        | Total (inclusive taxes)   |      |        | Total |        |



अभियंता सिविल 'अ'

५  
कॉलर २३/१२/१५  
ओएसडी २१/११/२०१६

#### सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर" "टिन नम्बर" लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या क्रियर भाड़ा नहीं दिया जायेगा.

| Sr No. | Description of item of work | Unit | Qty | Rate | Amount |
|--------|-----------------------------|------|-----|------|--------|
|--------|-----------------------------|------|-----|------|--------|

9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.

10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .

11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.

12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.

13. After completion of work the entire room may be cleaned by contractor at his own cost.

प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र