

INDIAN STATISTICAL INSTITUTE

DELHI CENTRE


Gram: STATISTICA, NEW DELHI

7, SJS, SANSANWAL MARG

Phone: 91-11-41493980

Fax: 91-11-41493981

Email: kalam@isid.ac.in



NEAR GUTUB HOTEL
KATWARIA SARAI

NEW DELHI-110016.

Tender Quotation


Ref; ISID/EMU/CABLE/2016-17/2

Date:28-04-2016

Name of the work: Supply and Laying of armoured cable works are to be carried out in our Institute premises. Kindly inspect the premises where the work has to be carried out and send your **sealed quotations** to reach us. **on or before 09-05-2016**. Tender will be received up to **03.00 pm** by The OSD, Indian Statistical Institute Delhi centre and will be opened on the same day at **03.30 PM**. The items for which rates are to be quoted are given in the enclosed statement. The Institute reserves the right to reject any or all the quotations or to allot parts of the work to different agencies without assigning any reason.

| S. No | Description of work | Qty | Unit | Rate | Amount |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|------|--------|
| 1 | Supply, Installation, testing and commissioning of 1100V, XLPE insulated and sheathed. Following Copper, Armoured, UG power cable with necessary earthing work. Make ;(Havells / Polycab/ Finolex) | | | | |
| | Cable laying In the soil with bricks on both side and top with sand cushion , including earth excavation work etc and completion of work as directed. | | | | |
| | 3C x 6 sq mm COPPER conductor (PVC) | 100 | mts | | |
| 2 | End termination of the following 1100 v grade XLPE insulated AR / copper conductor UG cables including supply of single compression cable gland crimping lugs and gland earthing. | | | | |
| | 3C x 6 sq mm COPPER conductor (PVC) | 2 | nos | | |

Karim Khan



Officer on Special Duty (A&F)

ISI Delhi Centre.

- Conditions:** 1) The work shall be carried out as per CPWD norms.
- 2) The work shall be carried out under the supervision of the Engineering In-Charge (Electrical).
 - 3) The material shall be got approved before use on work.
 - 4) The waste should be removed after completion of works.
 - 5) Contractor shall be furnished the TIN & PAN numbers, without TIN & PAN numbers Quotation will be not considered.

Copy to: E.A(Elect) /ISI Website/Account Officer/ISI notice board.