

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र

ग्राम स्टाटिस्टिका , नई दिल्ली
फोन : .41493984
फैक्स : 41493981
ईमेल : kalam@isid.ac.in



7, एस जे एस, सनसनवाल मार्ग,
क़तूब होटल के पास
कटवरिया सराय
नई दिल्ली

निविदा आमंत्रित सूचना

निविदा नं. D/ISI/CIVIL WORK/2016-2017/217

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 27/7/16 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

NAME OF WORK :-Painting Works and other civil works B-11 Flats in ISI campus , Delhi centre, New Delhi.

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Removing dry or oil bound distemper, water proffing cement paint and the like by scrapping, sand preparing and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	265.35		
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :				
	Old work (one or more coats)	sqm	254.23		
3	White washing with lime to give an even shade :				
	Old work (two or more coats)	sqm	41.174		
4	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	41.174		
5	Providing and applying white cement based putty of average thickness 1 mm , of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete				
	40 % paid of total quantity of item no. 1	sqm	106.14		
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :				
	With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	3.15		
7	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, loading to approved municipal dumping ground with prior permission. (dumping anywhere ISI is not responsible) taxes by contractor only.	sqm	1job		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shad: (Two or more coats on new work)	sqm	41.842		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
9	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	5.037		
10	Repainting G.I. pipes and fittings with synthetic enamel white paint with one coat of approved quality :	meter	13		
11	Finishing walls with Acrylic Smooth exterior paint of required shade :				
	Old work (One or more coat applied @ 0.90 ltr/10 sqm).	sqm	11.122		
12	existing window grill welding work	1 job	1		
13	Existing toilet wall tile joint filling by white cement work	sqm	5.037		
	Total (inclusive taxes)	Total			

Shane

अभियंता सिविल 'अ'

agbhatt

ओएसडी/हेड

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. Civil कार्य विवरण (Cpwd Specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition. The payment will be made in an actual basis.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कूल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ड्रलाई का अतिरिक्त किराया भाड़ा या कुरियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कूल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated(without any notice) at any stage without assisgning any reason.

प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र