

INDIAN STATISTICAL INSTITUTE  
DELHI CENTRE

Gram : STATISTICA, NEW DELHI  
Phone : 91-11-41493980  
Fax : 91-11-41493981  
Email : kalam@isid.ac.in



7, S. J. S. SANSANWAL MARG  
NEAR QUTAB HOTEL KATWARIA  
SARAI NEW DELHI-110016

NO.D/ISI/Civil Work /2016-17/ 208

Date : 14 /06/2016

QUOTATION

Sealed Quotation are invited from experienced contractors who have carried out the following type of works , so as to reach this offices on or before 23/06/2016 before 3.00 P.M. This Quotation shall be opened on the same date at 3.30 P.M. In front of parties whosoever is present.

Name of Work:- Waterproofing work of Canteen/Mess Building in ISI Campus, Delhi Centre, New Delhi-110016.

Sr No.	Description of work	Quantity	Unit	Rate/Unit	Amount
1	Removing the old tarfelt layer and clean -up bitumen to the surface by scraping and wire brushing complete. Including removing all loose debris, dust and check for hairlines cracks complete at all levels and as directed by Engineer-in-charge :	132.04	Sqm		
2	<p><b>Step1</b> Providing and laying integral cement based for waterproofing treatment with polymer modified mortor of appropriate proportion.</p> <p><b>Step2</b> Providing and laying one coat of Eniroof EMB/Black diluted with 20 % water.</p> <p><b>Step3</b> Providing and Laying Fibre Glass cloth on primer surface with 75 mm overlap at joint .</p> <p><b>Step4</b> Providing and laying one or more coat of Eniroof EMB/Black diluted with 10 % water on the Glass Fibre Cloth layer and</p>	132.04	sqm		

	allow it to cure for 24 hours completely. <b>Step5</b> Providing and laying second or more coat of Eniroof EMB/Black diluted with 10 % water on the Glass Fibre Cloth layer and allow it to cure for 24 hours completely. <b>Step6</b> Providing and laying one or more coat of Star Acrylic Polymer as a top coat.				
3	Malaba Removed out of the campus	1 job	L/S		
	Inclusive taxes			Total	

*Schanam*

Engineer Civil A

*Kaiser Alam*  
14/6/2016  
OSD

Terms and Conditions:-

1. The renderer must visit the site with prior appointment before the submission of the tender.
2. Work has to be completed within 15 days from receiving the work order.
3. Guidelines/ASTM standards must be followed.
4. All waste/malba must be removed from the premises of the ISI – Delhi Centre at the cost of the contractor.
5. ISI – Delhi Centre reserves the right to reject any tender without assigning any specific reason whatsoever.
6. Tenderers blacklisted ISI-Delhi Centre and CPWD shall not be considered.
7. Incomplete tenders will be summarily rejected.
8. Tenderers must submit the registration of PAN/TIN/ ETC. along with quotation.

Copy to :

1. ISI Website
2. Notice board