

भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र



ग्राम स्टैटिस्टिका , नई दिल्ली
फ़ोन : .41493984
फैक्स : 41493981
ईमेल : kalam@isid.ac.in

7 , एस जे एस , सनसनवाल मार्ग ,
कुतुब होटल के पास
कटवरिया सराय
नई दिल्ली

निविदा आमंत्रित सूचना


निविदा नं. D /ISI /CIVIL WORK /2016 -2017 / 244

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 30/11/2016 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Providing and Fixing of wooden door shutter and FRP door shutter kitchen cabinet and kitchen sink in ISI Campus Delhi Centre New Delh-110016

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:- 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	sqm	1.89		
	B-12				
2	Providing and fixing to existing door frames. 30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames	sqm	10.08		
	A-14				
	A-12				
	d-4				
3	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink with drain board 500x1130 mm bowl depth 250 mm	each	1		
	A-12				
4	Taking out of stainless still kitchen sink including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	1		
5	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below	each	7		
6	Applying priming coat : With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	sqm	4.4		
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	4.4		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
	c-4				
8	Providing and fixing in wall lining flat pressed three layer (medium density) particle board or graded wood Pre-laminated one side decorative lamination and other side balancing lamination Grade I, Type II, IS : 12823 marked, including priming coat on unexposed surface, with necessary fixing arrangement and screws etc. complete :				
	18 mm thick	sqm	2.772		
9	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :				
	2nd class teak wood				
	50 x 12 mm	meter	17.2		
10	providing and fixing of 8 mm bar for frames of cutting holes fixing in position etc. complete finishing .				
	weight 1 mtr = 0.400gram	kg	2.52		
11	Fixing old glass panes with wooden fillets/puty (including cost of fillets/putty)removig the old putty and finishing etc.	sqm	26.17		
	Total (inclusive taxes)			Total	


अभियंता सिविल 'अ' 22/11/16.

4
अभियंता सिविल
23/11/2016
ओएसडी

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमक्ष होना चाहिये .
3. कार्य आदेश मिलने के बाद 20 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर" "टिन नम्बर" लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition. The payment will be made in an actual basis.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्स एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या क्रियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट 4% सुरक्षित जमा राशि आपके कुल राशि पर 6 महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिम्मेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.
13. कांटेक्टर द्वारा लगाये गए आयरन वर्क (स्टील वर्क) कांटेक्टर और इंजीनियर सिविल के शमक्ष (weight) वजन किया जायेगा. वही एक्चुअल (weight) वजन माना जायेगा.
14. अगर (वर्क) काम में कुछ भी अनियमितता दिखाई देती है तो उसे तुरंत स्पष्टता के साथ करे. अन्यथा पेमेंट (PAYMENT) नहीं दिया जायेगा. कोटेशन के अनुसार ही पेमेंट दी जाएगी.