

भारतीय सांख्यिकी संस्थान

दिल्ली केंद्र



7, एस जे एस, सनसनवाल मार्ग,
कुतुब होटल के पास
कटवरिया सराय
नई दिल्ली

ग्राम स्टाटिस्टिका, नई दिल्ली

फोन : 41493984

फैक्स : 41493981

ईमेल : kalam@isid.ac.in

निविदा आमंत्रित सूचना

निविदा नं. D /ISI /CIVIL WORK /2016 -2017 / 220

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 05/08/2016 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .


Providing and Fixing of iron welded staircase in servant quarters no. 1 in ISI Campus Delhi Centre New Delh-110016

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge	cum	1.44		
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required				
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg	395.86		
	L-(40 X 40 X 5 First step				
	centre T support-40x40x6 mm				
	landing col supp-base				
	flats=40 mm wide 5.0 mm thick treads				
3	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer				
	G.I. pipes				
	50 mm od-2.2 mm thick	kg	19.5		
4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge				
	In cement mortar				
	one partition wall -9" thick	cum	0.186		
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level				
	Cement mortar 1:4 (1 cement :4 coarse sand)	sqm	0.81		
	CEMENT PLASTER (IN COARSE SAND)				
6	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 coarse sand)	sqm	1.62		

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	5.4		
8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, <u>disposed earth to be levelled and neatly dressed</u>				
	All kinds of soil	cum	0.063		
	concrete work				
9	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	0.084		
	Total (inclusive taxes)			Total	



अभियंता सिविल 'अ'


ओएसडी / एस

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमक्ष होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर " "टिन नम्बर " लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition. The payment will be made in an
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढुलाई का अतिरिक्त किराया भाड़ा या क्रियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.
13. कांटेक्टर द्वारा लगाये गए आयरन वर्क (स्टील वर्क) कांटेक्टर और इंजीनियर सिविल के शमक्ष (weight) वजन किया जायेगा. वही एक्यूअल (weight) वजन माना जायेगा.
14. अगर (वर्क) काम में कुछ भी अनियमितता दिखाई देती है तो उसे तुरंत स्पष्टता के साथ करे. अन्यथा पेमेंट (PAYMENT) नहीं दिया जायेगा. कोटेशन के अनुसार ही पेमेंट दी जाएगी.