## भारतीय सांख्यिकी संस्थान दिल्ली केंद्र

STATISTICAL
IN STATISTICAL

7, एस जे एस , सनसनवाल मार्ग , कृतुब होटल के पास कटवरिया सराय नई दिल्ली

ग्राम स्टास्टिस्टिका , नई दिल्ली फ़ोन : .41493984

फ़ान : .41493984 फैक्स : 41493981

ईमेल : kalam@isid.ac.in

## निविदा आमंत्रित सूचना

निविदा नं. D /ISI /CIVIL WORK /2016 -2017 / 2 1 6

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारिख 19 10712016 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Name of work - Painting and aluminimum door work in Library Building in ISI Campus Delhi Centre, New Delhi-110016.

Sr No.	Description of item of work	Unit	Qty	Rate	Amount
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	934.89		
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :	sqm	934.89		
	Old work (one or more coats)				
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	34.596		
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade:				
	Old work (one or more coats)	sqm	34.596		
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the lastered wall surface to prepare the surface even and smooth complete.				
	same as item 1-40% paid only	sqm	373.95		
	same as item 4	sqm	13.838		
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	sqm	131.308		
	One or more coats on old work				
7	Repainting G.I. pipes and fittings with synthetic enamel white paint with one coat of approved quality:	meter	30		
	50 mm diameter pipe			*	
8	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately):				

Sr No	Description of item of work	Unit	Qty	Rate	Amount
	For shutters of doors, windows & ventilators including providing and				
	fixing hinges/ pivots and making provision for fixing of fittings				
	wherever required including the cost of EPDM rubber / neoprene				
	gasket required (Fittings shall be paid for separately)				
	Powder coated aluminium (minimum thickness of powder coating 50	kg	48.09		
	micron)	-			
	Providing and fixing glazing in aluminium door, window, ventilator				
	shutters and partitions etc. with EPDM rubber / neoprene gasket etc.				
9	complete as per the architectural drawings and the directions of				
	engineer-in-charge . (Cost of aluminium snap beading shall be paid in				
	hasic item):		6.16		
	With float glass panes of 8 mm thickness	sqm	0.10		
	Providing and fixing double action hydraulic floor spring of approved				
	brand and manufacture conforming to IS: 6315, having brand logo				
	embossed on the body / plate with double spring mechanism and door				
	weight upto 125 kg, for doors, including cost of cutting floors,				
10	embedding in floors as required and making good the same matching				
	to the existing floor finishing and cover plates with brass pivot and		=		
	single piece M.S. sheet outer box with slide plate etc. complete as per				
	the direction of Engineer-in-charge.			T <sub>0</sub>	
	With stainless steel cover plate minimum 1.25 mm thickness	each	1		
	Providing and fixing aluminium round shape handle of outer dia 100				
11	mm with SS screws etc. complete as per direction of Engineerin-charge			>:	
	Powder coated minimum thickness 50 micron aluminium	each	2		
	Providing and fixing 100mm brass locks (best make of approved				
12	quality) for aluminium doors including necessary cutting and making	each	1		
	good etc. complete. Providing and fixing aluminium hanging floor door stopper, ISI marked,			-	
	anodised (anodic coating not less than grade AC 10 as per IS : 1868)				
13	transparent or dyed to required colour and shade, with necessary				
	screws etc. complete.			1	
		each	2		1
	Twin rubber stopper Providing and fixing aluminium tower bolts, ISI marked, anodised	eacii	2		
	(anodic coating not less than grade AC 10 as per IS : 1868 ) transparent				
14	or dyed to required colour or shade, with necessary screws etc.				-
	complete:				
		each	2		
	250x10 mm	eacii			
	Providing and fixing ISI marked aluminium butt hinges anodised				
15	(anodic coating not less than grade AC 10 as per IS : 1868) transparent				
	or dyed to required colour or shade with necessary screws etc.				
	complete: 100x75x4 mm	each	3		
	Providing and fixing aluminium sliding door bolts, ISI marked anodised	50011			
16	(anodic coating not less than grade AC 10 as per IS : 1868), transparent				
	or dyed to required colour or shade, with nuts and screws etc.				
	complete :				
	300x16 mm	each	1		
	Filling the gap in between aluminium frame & adjacent RCC/ Brick/				
	Stone work by providing weather silicon sealant over backer rod of				
17	approved quality as per architectural drawings and direction of				
	Engineer-in-charge complete.				
	Upto 5mm depth and 5 mm width	meter	7.8		
	AND TOWNS OF THE PROPERTY OF T				

Sr No	Description of item of work	Unit	Qty	Rate	Amount

5 Chanar P

अभियंता सिविल 'अ'

A 212 1 2018

सचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .

- 2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमक्श होना चाहिये .
- 3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
  - 4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ ''डी वट'' ''पन नम्बर '' ''टिन नम्बर '' लगाना अनिवार्य है .
- 5. The quantity will be increased or decreased as per the actual site condition. The payment will be made in an actual basis.
- 6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
- 7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
- 8. माल ढलाई का अतिरिक्त किराया भाड़ा या क्रियर भाड़ा नहीं दिया जायेगा.
- 9. सिक्योरिटी डिपाजिट ५% स्रक्षित जमा राशि आपके क्ल राशि पर ६ महीने के लिए वैध रहेगी.
- 10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
- 11.काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
- 12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.

प्रति :-

- 1. स्चना पलट
- 1. वेब स्थल आई एस आई दिल्ली केन्द्र