


भारतीय सांख्यिकी संस्थान
दिल्ली केंद्र

ग्राम स्टाटिस्टिका, नई दिल्ली

फ़ोन : 41493984

फैक्स : 41493981

ईमेल : kalam@isid.ac.in



7, एस जे एस, सनसनवाल मार्ग,
क़्लब होटल के पास
कटवरिया सराय
नई दिल्ली

निविदा आमंत्रित सूचना

निविदा नं. D/ISI/CIVIL WORK/2016-2017/

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारीख 24/01/2017 या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Plumbing work FACULTY BLOCK/D-25/B-10/D-19/D-26/D-36/D-30/D-31 Over Tankin ISI Campus Delhi Centre, New Delhi-110016.

| Sr No. | Description of item of work | Unit | Qty | Rate | Amount |
|--------|--|-----------|------|------|--------|
| 1 | Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. | | | | |
| | Circular tank(500 ltr)(syntex make) | per litre | 4000 | | |
| | Providing and Fixing of GI Fitting :- | | | | |
| 2 | tank nipple 20 mm | each | 17 | | |
| 3 | tank nipple 12 mm | each | 6 | | |
| 4 | union-20 mm | each | 17 | | |
| 5 | union-12 mm | each | 6 | | |
| 6 | socket-20 MM | each | 21 | | |
| 7 | socket-12 MM | each | 2 | | |
| 8 | nipple-12 mm-L-2" | each | 4 | | |
| 9 | nipple-12 mm-L-3" | each | 8 | | |
| 10 | nipple-12 mm-L-4" | each | 2 | | |
| 11 | nipple-12 mm-L-6" | each | 2 | | |
| 12 | nipple-12 mm-L-12" | each | 7 | | |
| 13 | nipple-20 mm-L-2" | each | 3 | | |
| 14 | nipple-20 mm-L-3" | each | 9 | | |
| 15 | nipple-20 mm-L-4" | each | 17 | | |
| 16 | nipple-20 mm-L-6" | each | 1 | | |
| 17 | nipple-20 mm-L-12" | each | 1 | | |
| 18 | Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : | | | | |
| | 20 mm nominal bore | each | 17 | | |
| | 12 mm nominal bore | each | 6 | | |
| 19 | Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : | | | | |
| | 20 mm nominal bore | each | 7 | | |
| 20 | HEX NIPPLE -20 MM | each | 6 | | |
| 21 | Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. | | | | |
| | 15 mm dia nominal bore | meter | 6 | | |

| | | | | | |
|--|-------------------------|-------|-----|-------|--|
| | 20 mm dia nominal bore | meter | 1.8 | | |
| | Total (inclusive taxes) | | | Total | |

S. Charan

अभियंता सिविल 'अ'

S. Charan
ओएसडी
17/1/2017

सूचना

1. प्रस्ताव देने के पहले विवरणकर्ता(quotationer) का जगह को देखना अनिवार्य है .
2. कार्य विवरण(specification) सहित व सिविल अभियंता के शमकश होना चाहिये .
3. कार्य आदेश मिलने के बाद 15 दिन के भीतर कार्य समाप्त होना चाहिए.
4. विवरणकर्ता(quotationer) विवरण फार्म(quotation) के साथ "डी वट" "पन नम्बर" "टिन नम्बर" लगाना अनिवार्य है .
5. The quantity will be increased or decreased as per the actual site condition.
6. विवरण फार्म(quotation) सिग्नेचर किये बगैर और स्टाम्प लगाये बगैर मिला तो सीधे सीधे निरस्त किया जाएगा .
7. कोटेशन में दिए गए आपके कुल राशि पर टैक्सेज एप्लीकेबल रहेंगे.
8. माल ढलाई का अतिरिक्त किराया भाड़ा या क्रियर भाड़ा नहीं दिया जायेगा.
9. सिक्योरिटी डिपोजिट ५% सुरक्षित जमा राशि आपके कुल राशि पर ६ महीने के लिए वैध रहेगी.
10. एडवांस राशि काम के पहले या बाद में एप्लीकेबल नहीं रहेंगे .
11. काम करते समय किसी भी प्रकार का हादसे के लिए ISI Delhi Centre जिमेदार नहीं रहेगी.
12. The ISI Delhi Centre reserve the right the whole tender process may be treated as a cancelled/terminated at any stage without assisgning any reason.
13. Malaba removing outside the campus at own cost.

प्रति :-

1. सूचना पलट

1. वेब स्थल आई एस आई दिल्ली केन्द्र