

INDIAN STATISTICAL INSTITUTE

DELHI CENTRE

Gram: STATISTICA, NEW DELHI

7, SJS, SANSANWAL MARG

Phone: 91-11-41493980

Fax: 91-11-41493981

Email: kalam@isid.ac.in



NEAR QUTUB HOTEL
KATWARIA SARAI

NEW DELHI-110016.

ISID/EMU/Street light/2017-18/ 27

Date:08-11-2017

निविदा दर सूची Tender Quotation

कार्य का नाम : स्ट्रीट लाईट पोलस, केबल्स तथा लाईट फिक्सचर तथा अन्य विभिन्न प्रकार के कार्यों को कार्यालय परिसर में ही किया जाना है। कृपया उस परिक्षेत्र का निरीक्षण कर लें जहां पर कार्य किया जाना है तथा अपनी मोहरबंद निविदाएं (Sealed Quotations) हमारे पास 22/11/2017 को 3 बजे तक या उससे पहले भेज दें। निविदाएं विशेष कार्य अधिकारी भारतीय सांख्यिकीय संस्थान द्वारा 3 बजे तक प्राप्त की जाएंगी तथा उसी दिन 3.30 बजे खोली जाएंगी। जिन मदों के लिए दरें उद्धृत की जानी हैं वे संलग्न विवरणी में हैं। संस्थान को यह अधिकार है कि वह बिना कोई कारण बताए एक या सभी निविदाओं को अस्वीकृत कर दे या कार्य के हिस्सों को अलग अलग एजेंसियों को आवंटित कर दे।

Name of the work: Street light poles, cables and light fixture and other miscellaneous works are to be carried out in our Institute premises. Kindly inspect the premises where the work has to be carried out and send your **sealed quotations** to reach us **on or before 22.11.2017**. Tender will be received up to **03.00 pm** by The **Officer on Special Duty**, Indian Statistical Institute Delhi centre and will be opened on the same day at **03.30 PM**. The items for which rates are to be quoted are given in the enclosed statement. The Institute reserves the right to reject any or all the quotations or to allot parts of the work to different agencies without assigning any reason.

S. No	Description of work	Qty	Unit	Rate	Amount
1	Supply, Installation, testing and commissioning of 1100V, XLPE insulated and sheathed. Following Copper, Armoured, UG power cable with necessary earthing work. Make ;(Havells / Polycab/ Finolex)				
	Cable laying In the soil with bricks on both side and top with sand cushion , including earth excavation work etc and completion of work as directed.				
1.1	3C x 1.5 sq mm COPPER conductor (PVC)	250	mts		
1.2	End termination of the following 1100 v grade XLPE insulated AR / copper conductor UG cables including supply of single compression cable gland crimping lugs and gland earthing.				
1.2.1	3C x 1.5 sq mm COPPER conductor (PVC)	6	nos		

