

INDIAN STATISTICAL INSTITUTE

DELHI CENTRE

Gram: STATISTICA, NEW DELHI

7, SJS, SANSANWAL MARG

Phone: 91-11-41493980

Fax: 91-11-41493981

Email: kalam@isid.ac.in



NEAR QUTUB HOTEL
KATWARIA SARAI

NEW DELHI-110016.

Tender Quotation


ISID/EMU MTCE/ Tender / 2017-18/08

16th June, 2017

Name of the work: Special preventive maintenance works substation are to be carried out in our Institute premises. Kindly inspect the premises where the work has to be carried out and send your **sealed quotations** to reach us **on or before 04.07.2017**. Tender will be received up to **03.00 pm** by The **Officer on Special Duty**, Indian Statistical Institute Delhi centre and will be opened on the same day at **03.30 PM**. The items for which rates are to be quoted are given in the enclosed statement. The Institute reserves the right to reject any or all the quotations or to allot parts of the work to different agencies without assigning any reason.

S. No	Description of work	Qty	Unit	Rate	Amount
1	Filtration of Tr oil for 750 KVA, 11KV / 433V, 3Phase, each 720 lts capacity with neat work man ship and as directed by engineer in charge.	425	Lts		
2	BDV and Acidity test (2 x 1 times)	1	Nos		
3	Topping up of Transformer oil as directed	100	Lts		
4	Testing of earth electrode, supply and fixing of new SS bolt, nuts and washers with anti corrosive materials.	25	Nos		
5	Testing and calibration of following protective relays and meters.				
	2TJM10	3	Nos		
	Buzh relay	1	Nos		
	Tr Temp. relay	2	Nos		
	Meters	10	Nos		
6	Checking, cleaning, servicing and tightening of all bolt and nuts in MV Panel placed in 11 kv substation.	1	Set		

7	Primary injection test for HT side	2	Nos.		
8	Checking, cleaning servicing and tightening of all bolt and nuts in various 3 phase raw power / UPS, 6 / 8 12 WAY DB's as directed by engineer in charge	30	Nos		
9	Checking, cleaning servicing and tightening of all bolt and nuts in various 3 phase raw power / UPS distribution power panels as directed by engineer in charge.	15	Nos		
10	Supply and fixing of analog voltmeter range 0-500V	5	Nos		
11	Supply and fixing of analog ammeter range 0-100 amps AC	5	Nos		
12	Supply and fixing of SELEC Make VAF 32 Model, 96x96 Voltage, Amps, Frequency measuring meter as directed by engineer in charge.	2	Nos		
13	Checking, cleaning, servicing and tightening of all bolt and nuts in various 3 phase raw power feeder pillar power panels as directed by engineering in charge.	4	Nos		
14	Re-painting of various existing 3 phase feeder pillar with two coating of anti-corrosive bimastic paint of approved quality. Existing colour. Make; Asian, Berger, Nerolac	4	Nos		
15	Finishing with Acrylic smooth exterior paint of required shade. New work (Two coat applied @1.67 ltrs / 10 sqm over and including priming coat of exterior primer applied @2.2 kg / 10 sqm, White colour. Make; Asian, Berger, Nerolac	80	Sqm		
TOTAL				Rs.	


 16/6/2019
Officer on Special- Duty
ISI Delhi Centre

Terms and Condition:

- 1) The work shall be completed within one month from the date of receipt of work order.
- 2) The work will be done under the supervision of Engrg. Asst. (Electrical) 'A'
- 3) Waste should be removed after completion of work.
- 4) The rates are inclusive of all taxes.
- 5) The deviation allowed 10% .
- 6) Any of the work found in bad quality or result does not conform to the specification, the defective works have to be replaced immediately. No extra payment will be made.

Copy to: Accounts Officer