

भारतीय सांख्यिकीय संस्थान
दिल्ली केन्द्र

ग्राम: स्टाटिस्टिका, नई दिल्ली
फोन: 91.11.41493987
फेक्स: 91.11.41493981
ईमेल : kalam@isid.ac.in



7, एसजेएस, सनसनवाल मार्ग
कुतुब होटल के पास
कटवारिया सराय
नई दिल्ली-110016

NOTICE INVITING TENDER

Tender No. D/ISI/CIVIL WORK/2015-17/184

मोहरबंद लिफाफे में भरे हुए विवरण(quotation) आमंत्रित किए जाते हैं . विवरण(quotation) तारिख 20/4/16

या उससे पहले इस कार्यालय को 3.00 बजे तक मिलने चाहिये . विवरण(quotation) उसी दिन आपके समक्ष या आपके अनुपस्थिति में 3.30 बजे खोले जायेंगे .

Name of work :- Providing and fixing of uPVC Pipelines and new gate valves work near harvesting tank, in ISI Campus Delhi Centre New Delhi-110016

sr No.	Description of item of work	Unit	Qty	Rate	Amount
	u.P.V.C. PIPES-3"-ASTRAL MAKE-SCH-40				
1	Providing and fixing u Polyvinyl Chloride (uPVC) pipes, water supply, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step uPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	meter	4		
2	Providing and fixing of socket for water supply, including fixing the pipe. This includes jointing of pipes & fittings with one step uPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	each	3		
3	Providing and fixing of TEE for water supply, including fixing the pipe. This includes jointing of pipes & fittings with one step uPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	each	1		
4	Providing and fixing of Male Adaptor(pvc thread) for water supply, including fixing the pipe. This includes jointing of pipes & fittings with one step uPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	each	4		
5	Providing and Fixing of Gate Valve - Zoloto/leader/sant/higher of one. This includes jointing of pipes & fittings with one step uPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	each	2		

sr No.	Description of item of work	Unit	Qty	Rate	Amount
6	Providing and fixing of Union for water supply, including fixing the pipe. This includes jointing of pipes & fittings with one step uPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	each	2		
7	Providing and fixing of Elbow 90 deg for water supply, including fixing the pipe. This includes jointing of pipes & fittings with one step uPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	each	3		
8	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :				
	All kinds of soil				
	Pipes, cables etc. exceeding 300 mm dia but not exceeding 600 mm	meter	4.6		
9	Making connection of G.I./pvc/upvc distribution branch with G.I.main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
	50 to 80 mm nominal bore	each	3		
10	Demolishing lime concrete manually/ by mechanical means and disposal of material within 50 metres lead as per direction of Engineer-in-charge.	cum	0.1		
11	Dismantling G.I./pvc/cpvc pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	Above 40 mm nominal bore	meter	4		
12	Dismantling of Gate valve including stacking of useful materials within a lead of 50 metres				
	Up to 150 mm diameter	each	2		
	inclusive taxes as per applicable			Total	

अभियंता सिविल 'अ'

Schavan

११ दिनांक ३१ मई
ओएसडी